### **Features**

- High-performance, Low-power 8/16-bit Atmel® AVR® XMEGA™ Microcontroller
- Non-volatile Program and Data Memories
  - 256 KB of In-System Self-Programmable Flash
  - 8 KB Boot Code Section with Independent Lock Bits
  - 4 KB EEPROM
  - 16 KB Internal SRAM
- Peripheral Features
  - Four-channel DMA Controller with support for external requests
  - Eight-channel Event System
  - Seven 16-bit Timer/Counters

Four Timer/Counters with 4 Output Compare or Input Capture channels Three Timer/Counters with 2 Output Compare or Input Capture channels **High-Resolution Extension on all Timer/Counters** Advanced Waveform Extension on one Timer/Counter

- Six USARTs

IrDA modulation/demodulation for one USART

- Two Two-Wire Interfaces with dual address match (I<sup>2</sup>C and SMBus compatible)
- Two SPI (Serial Peripheral Interface) peripherals
- AES and DES Crypto Engine
- 32-bit Real Time Counter with separate Oscillator and Battery Backup System
- Two Eight-channel, 12-bit, 2 Msps Analog to Digital Converters
- One Two-channel, 12-bit, 1 Msps Digital to Analog Converters
- Four Analog Comparators with Window compare function
- External Interrupts on all General Purpose I/O pins
- Programmable Watchdog Timer with Separate On-chip Ultra Low Power Oscillator
- **Special Microcontroller Features** 
  - Power-on Reset and Programmable Brown-out Detection
  - Internal and External Clock Options with PLL
  - Programmable Multi-level Interrupt Controller
  - Sleep Modes: Idle, Power-down, Standby, Power-save, Extended Standby
  - Advanced Programming, Test and Debugging Interfaces JTAG (IEEE 1149.1 Compliant) Interface for test, debug and programming

PDI (Program and Debug Interface) for programming and debugging

- I/O and Packages
  - 49 Programmable I/O Lines
  - 64-lead TQFP
  - 64-pad QFN/MLF
- Operating Voltage
  - -1.6 3.6V
- Speed performance
  - 0 12 MHz @ 1.6 3.6V
  - 0 32 MHz @ 2.7 3.6V

# Typical Applications

- · Industrial control
- ZiaBee
- Hand-held battery applications

- Factory automation
- Power tools

- Building control
- Motor control
- HVAC

- Board control
- Networking

Climate control

Metering

- White Goods
- Optical
- Medical Applications



# 8/16-bit **AVR XMEGA A3B Microcontroller**

ATxmega256A3B

# **Preliminary**

Not recommended for new designs - Use ATxmega256A3BU

8116J-AVR-06/2013



# **Ordering Information**

Ordering Code	Flash	E <sup>2</sup>	SRAM	Speed (MHz)	Power Supply	Package <sup>(1)(2)(3)</sup>	Temp
ATxmega256A3B-AU	256 KB + 8 KB	4 KB	16 KB	32	1.6 - 3.6V	64A	-40°C - 85°C
ATxmega256A3B-MH	256 KB + 8 KB	4 KB	16 KB	32	1.6 - 3.6V	64M2	-40 C - 65 C


- 1. This device can also be supplied in wafer form. Please contact your local Atmel sales office for detailed ordering information.
- 2. Pb-free packaging, complies to the European Directive for Restriction of Hazardous Substances (RoHS directive). Also Halide free and fully Green.
- 3. For packaging information, see "Electrical Characteristics" on page 64.

	Package Type
64A	64-Lead, 14 x 14 mm Body Size, 1.0 mm Body Thickness, 0.8 mm Lead Pitch, Thin Profile Plastic Quad Flat Package (TQFP)
64M2	64-Pad, 9 x 9 x 1.0 mm Body, Lead Pitch 0.50 mm, 7.65 mm Exposed Pad, Micro Lead Frame Package (MLF)



# 2. Pinout/Block Diagram

Figure 2-1. Block diagram and pinout.



Notes: 1. For full details on pinout and pin functions refer to "Pinout and Pin Functions" on page 50.

2. The large center pad underneath the QFN/MLF package should be soldered to ground on the board to ensure good mechanical stability.

# 3. Overview

The XMEGA<sup>™</sup>A3B is a family of low power, high performance and peripheral rich CMOS 8/16-bit microcontrollers based on the AVR<sup>®</sup> enhanced RISC architecture. By executing powerful instructions in a single clock cycle, the XMEGA A3B achieves throughputs approaching 1 Million Instructions Per Second (MIPS) per MHz allowing the system designer to optimize power consumption versus processing speed.

The AVR CPU combines a rich instruction set with 32 general purpose working registers. All the 32 registers are directly connected to the Arithmetic Logic Unit (ALU), allowing two independent registers to be accessed in one single instruction, executed in one clock cycle. The resulting architecture is more code efficient while achieving throughputs many times faster than conventional single-accumulator or CISC based microcontrollers.

The XMEGA A3B devices provides the following features: In-System Programmable Flash with Read-While-Write capabilities, Internal EEPROM and SRAM, four-channel DMA Controller, eight-channel Event System, Programmable Multi-level Interrupt Controller, 49 general purpose I/O lines, 32-bit Real Time Counter (RTC) with Battery Backup System, seven flexible 16-bit Timer/Counters with compare modes and PWM, six USARTs, two Two Wire Serial Interfaces (TWIs), two Serial Peripheral Interfaces (SPIs), AES and DES crypto engine, two 8-channel, 12-bit ADCs with optional differential input with programmable gain, one 2-channel 12-bit DAC, four analog comparators with window mode, programmable Watchdog Timer with separate Internal Oscillator, accurate internal oscillators with PLL and prescaler and programmable Brown-Out Detection.

The Program and Debug Interface (PDI), a fast 2-pin interface for programming and debugging, is available. The devices also have an IEEE std. 1149.1 compliant JTAG test interface, and this can also be used for On-chip Debug and programming.


The XMEGA A3B devices have five software selectable power saving modes. The Idle mode stops the CPU while allowing the SRAM, DMA Controller, Event System, Interrupt Controller and all peripherals to continue functioning. The Power-down mode saves the SRAM and register contents but stops the oscillators, disabling all other functions until the next TWI or pin-change interrupt, or Reset. In Power-save mode, the asynchronous Real Time Counter continues to run, allowing the application to maintain a timer base while the rest of the device is sleeping. In Standby mode, the Crystal/Resonator Oscillator is kept running while the rest of the device is sleeping. This allows very fast start-up from external crystal combined with low power consumption. In Extended Standby mode, both the main Oscillator and the Asynchronous Timer continue to run. To further reduce power consumption, the peripheral clock to each individual peripheral can optionally be stopped in Active mode and Idle sleep mode.

The device is manufactured using Atmel's high-density nonvolatile memory technology. The program Flash memory can be reprogrammed in-system through the PDI or JTAG. A Bootloader running in the device can use any interface to download the application program to the Flash memory. The Bootloader software in the Boot Flash section will continue to run while the Application Flash section is updated, providing true Read-While-Write operation. By combining an 8/16-bit RISC CPU with In-System Self-Programmable Flash, the Atmel XMEGA A3B is a powerful microcontroller family that provides a highly flexible and cost effective solution for many embedded applications.

The XMEGA A3B devices are supported with a full suite of program and system development tools including: C compilers, macro assemblers, program debugger/simulators, programmers, and evaluation kits.

#### 3.1 **Block Diagram**

Figure 3-1. XMEGA A3B Block Diagram



# 4. Resources

A comprehensive set of development tools, application notes and datasheets are available for download on http://www.atmel.com/avr.

# 4.1 Recommended reading

- XMEGA A Manual
- XMEGA Application Notes

This device data sheet only contains part specific information and a short description of each peripheral and module. The XMEGA A Manual describes the modules and peripherals in depth. The XMEGA application notes contain example code and show applied use of the modules and peripherals.

The XMEGA A Manual and Application Notes are available from http://www.atmel.com/avr.

# 5. Disclaimer

For devices that are not available yet, typical values contained in this datasheet are based on simulations and characterization of other AVR XMEGA microcontrollers manufactured on the same process technology. Min. and Max values will be available after the device is characterized.

# **AVR CPU**


#### 6.1 **Features**

- 8/16-bit high performance AVR RISC Architecture
  - 138 instructions
  - Hardware multiplier
- 32x8-bit registers directly connected to the ALU
- Stack in SRAM
- Stack Pointer accessible in I/O memory space
- . Direct addressing of up to 16M Bytes of program and data memory
- True 16/24-bit access to 16/24-bit I/O registers
- Support for 8-, 16- and 32-bit Arithmetic
- Configuration Change Protection of system critical features

#### 6.2 Overview

The XMEGA A3B uses the 8/16-bit AVR CPU. The main function of the CPU is program execution. The CPU must therefore be able to access memories, perform calculations and control peripherals. Interrupt handling is described in a separate section. Figure 6-1 on page 7 shows the CPU block diagram.

Figure 6-1. CPU block diagram



The AVR uses a Harvard architecture - with separate memories and buses for program and data. Instructions in the program memory are executed with a single level pipeline. While one instruction is being executed, the next instruction is pre-fetched from the program memory. This



concept enables instructions to be executed in every clock cycle. The program memory is In-System Self-Programmable Flash memory.

# 6.3 Register File

The fast-access Register File contains 32 x 8-bit general purpose working registers with single clock cycle access time. This allows single-cycle Arithmetic Logic Unit (ALU) operation. In a typical ALU cycle, the operation is performed on two Register File operands, and the result is stored back in the Register File.

Six of the 32 registers can be used as three 16-bit address register pointers for data space addressing - enabling efficient address calculations. One of these address pointers can also be used as an address pointer for look up tables in Flash program memory.

# 6.4 ALU - Arithmetic Logic Unit

The high performance Arithmetic Logic Unit (ALU) supports arithmetic and logic operations between registers or between a constant and a register. Single register operations can also be executed. Within a single clock cycle, arithmetic operations between general purpose registers or between a register and an immediate are executed. After an arithmetic or logic operation, the Status Register is updated to reflect information about the result of the operation.

The ALU operations are divided into three main categories – arithmetic, logical, and bit-functions. Both 8- and 16-bit arithmetic is supported, and the instruction set allows for easy implementation of 32-bit arithmetic. The ALU also provides a powerful multiplier supporting both signed and unsigned multiplication and fractional format.

# 6.5 Program Flow

When the device is powered on, the CPU starts to execute instructions from the lowest address in the Flash Program Memory '0'. The Program Counter (PC) addresses the next instruction to be fetched. After a reset, the PC is set to location '0'.

Program flow is provided by conditional and unconditional jump and call instructions, capable of addressing the whole address space directly. Most AVR instructions use a 16-bit word format, while a limited number uses a 32-bit format.

During interrupts and subroutine calls, the return address PC is stored on the Stack. The Stack is effectively allocated in the general data SRAM, and consequently the Stack size is only limited by the total SRAM size and the usage of the SRAM. After reset the Stack Pointer (SP) points to the highest address in the internal SRAM. The SP is read/write accessible in the I/O memory space, enabling easy implementation of multiple stacks or stack areas. The data SRAM can easily be accessed through the five different addressing modes supported in the AVR CPU.

# 7. Memories

### 7.1 Features

- Flash Program Memory
  - One linear address space
  - In-System Programmable
  - Self-Programming and Bootloader support
  - Application Section for application code
  - Application Table Section for application code or data storage
  - Boot Section for application code or bootloader code
  - Separate lock bits and protection for all sections
  - Built in fast CRC check of a selectable flash program memory section
- Data Memory
  - One linear address space
  - Single cycle access from CPU
  - SRAM
  - EEPROM

Byte and page accessible

Optional memory mapping for direct load and store

- I/O Memory

Configuration and Status registers for all peripherals and modules 16 bit-accessible General Purpose Register for global variables or flags

- Bus arbitration

Safe and deterministic handling of CPU and DMA Controller priority

- Separate buses for SRAM, EEPROM, I/O Memory and External Memory access
   Simultaneous bus access for CPU and DMA Controller
- Production Signature Row Memory for factory programmed data

Device ID for each microcontroller device type

Serial number for each device

Oscillator calibration bytes

ADC, DAC and temperature sensor calibration data

User Signature Row

One flash page in size

Can be read and written from software

Content is kept after chip erase

### 7.2 Overview

The AVR architecture has two main memory spaces, the Program Memory and the Data Memory. In addition, the XMEGA A3B features an EEPROM Memory for non-volatile data storage. All three memory spaces are linear and require no paging. The available memory size configurations are shown in "Ordering Information" on page 2. In addition each device has a Flash memory signature row for calibration data, device identification, serial number etc.

Non-volatile memory spaces can be locked for further write or read/write operations. This prevents unrestricted access to the application software.



# 7.3 In-System Programmable Flash Program Memory

The XMEGA A3B devices contain On-chip In-System Programmable Flash memory for program storage, see Figure 7-1 on page 10. Since all AVR instructions are 16- or 32-bits wide, each Flash address location is 16 bits.

The Program Flash memory space is divided into Application and Boot sections. Both sections have dedicated Lock Bits for setting restrictions on write or read/write operations. The Store Program Memory (SPM) instruction must reside in the Boot Section when used to write to the Flash memory.

A third section inside the Application section is referred to as the Application Table section which has separate Lock bits for storage of write or read/write protection. The Application Table section can be used for storing non-volatile data or application software.

Figure 7-1. Flash Program Memory (Hexadecimal address)


# 

The Application Table Section and Boot Section can also be used for general application software.

# 7.4 Data Memory


The Data Memory consists of the I/O Memory, EEPROM and SRAM memories, all within one linear address space, see Figure 7-2 on page 10. To simplify development, the memory map for all devices in the family is identical and with empty, reserved memory space for smaller devices.

Figure 7-2. Data Memory Map (Hexadecimal address)





Data Memory Map (Hexadecimal address) Figure 7-2.



#### 7.4.1 I/O Memory

All peripherals and modules are addressable through I/O memory locations in the data memory space. All I/O memory locations can be accessed by the Load (LD/LDS/LDD) and Store (ST/STS/STD) instructions, transferring data between the 32 general purpose registers in the CPU and the I/O Memory.

The IN and OUT instructions can address I/O memory locations in the range 0x00 - 0x3F directly.

I/O registers within the address range 0x00 - 0x1F are directly bit-accessible using the SBI and CBI instructions. The value of single bits can be checked by using the SBIS and SBIC instructions on these registers.

The I/O memory address for all peripherals and modules in XMEGA A3B is shown in the "Peripheral Module Address Map" on page 57.

#### 7.4.2 **SRAM Data Memory**

The XMEGA A3B devices have internal SRAM memory for data storage.

#### 7.4.3 **EEPROM Data Memory**

The XMEGA A3B devices have internal EEPROM memory for non-volatile data storage. It is addressable either in a separate data space or it can be memory mapped into the normal data memory space. The EEPROM memory supports both byte and page access.

# 7.5 Production Signature Row

The Production Signature Row is a separate memory section for factory programmed data. It contains calibration data for functions such as oscillators and analog modules.

The production signature row also contains a device ID that identify each microcontroller device type, and a serial number that is unique for each manufactured device. The device ID for the available XMEGA A3 devices is shown in Table 7-1 on page 12. The serial number consist of the production LOT number, wafer number, and wafer coordinates for the device.

The production signature row can not be written or erased, but it can be read from both application software and external programming.

**Table 7-1.** Device ID bytes for XMEGA A3B device.

Device		Device ID bytes	
	Byte 2	Byte 1	Byte 0
ATxmega256A3B	43	98	1E

# 7.6 User Signature Row

The User Signature Row is a separate memory section that is fully accessible (read and write) from application software and external programming. The user signature row is one flash page in size, and is meant for static user parameter storage, such as calibration data, custom serial numbers or identification numbers, random number seeds etc. This section is not erased by Chip Erase commands that erase the Flash, and requires a dedicated erase command. This ensures parameter storage during multiple program/erase session and on-chip debug sessions.

#### 7.7 Flash and EEPROM Page Size

The Flash Program Memory and EEPROM data memory are organized in pages. The pages are word accessible for the Flash and byte accessible for the EEPROM.

Table 7-2 on page 13 shows the Flash Program Memory organization. Flash write and erase operations are performed on one page at a time, while reading the Flash is done one byte at a time. For Flash access the Z-pointer (Z[m:n]) is used for addressing. The most significant bits in the address (FPAGE) give the page number and the least significant address bits (FWORD) give the word in the page.

Table 7-2. Number of words and Pages in the Flash.

Devices	Flash Size	Page Size	FWORD	FPAGE	Applio	cation	Вс	oot
		(words)			Size	No of Pages	Size	No of Pages
ATxmega256A3B	256 KB + 8 KB	256	Z[8:1]	Z[18:9]	256 KB	512	8 KB	16

Table 7-3 on page 13 shows EEPROM memory organization for the XMEGA A3B devices. EEPROM write and erase operations can be performed one page or one byte at a time, while reading the EEPROM is done one byte at a time. For EEPROM access the NVM Address Register (ADDR[m:n]) is used for addressing. The most significant bits in the address (E2PAGE) give the page number and the least significant address bits (E2BYTE) give the byte in the page.

**Table 7-3.** Number of Bytes and Pages in the EEPROM.

Devices	EEPROM	Page Size	E2BYTE	E2PAGE	No of Pages
	Size	(Bytes)			
ATxmega256A3B	4 KB	32	ADDR[4:0]	ADDR[11:5]	128

# 8. DMAC - Direct Memory Access Controller

### 8.1 Features

- · Allows High-speed data transfer
  - From memory to peripheral
  - From memory to memory
  - From peripheral to memory
  - From peripheral to peripheral
- 4 Channels
- From 1 byte and up to 16M bytes transfers in a single transaction
- Multiple addressing modes for source and destination address
  - Increment
  - Decrement
  - Static
- 1, 2, 4, or 8 byte Burst Transfers
- Programmable priority between channels

### 8.2 Overview

The XMEGA A3B has a Direct Memory Access (DMA) Controller to move data between memories and peripherals in the data space. The DMA controller uses the same data bus as the CPU to transfer data.

It has 4 channels that can be configured independently. Each DMA channel can perform data transfers in blocks of configurable size from 1 to 64K bytes. A repeat counter can be used to repeat each block transfer for single transactions up to 16M bytes. Each DMA channel can be configured to access the source and destination memory address with incrementing, decrementing or static addressing. The addressing is independent for source and destination address. When the transaction is complete the original source and destination address can automatically be reloaded to be ready for the next transaction.

The DMAC can access all the peripherals through their I/O memory registers, and the DMA may be used for automatic transfer of data to/from communication modules, as well as automatic data retrieval from ADC conversions, data transfer to DAC conversions, or data transfer to or from port pins. A wide range of transfer triggers are available from the peripherals, Event System and software. Each DMA channel has different transfer triggers.

To allow for continuous transfers, two channels can be interlinked so that the second takes over the transfer when the first is finished and vice versa.

The DMA controller can read from memory mapped EEPROM, but it cannot write to the EEPROM or access the Flash.

# Event System

### 9.1 Features

- · Inter-peripheral communication and signalling with minimum latency
- CPU and DMA independent operation
- 8 Event Channels allows for up to 8 signals to be routed at the same time
- Events can be generated by
  - Timer/Counters (TCxn)
  - Real Time Counter (RTC)
  - Analog to Digital Converters (ADCx)
  - Analog Comparators (ACx)
  - Ports (PORTx)
  - System Clock (Clk<sub>SYS</sub>)
  - Software (CPU)
- · Events can be used by
  - Timer/Counters (TCxn)
  - Analog to Digital Converters (ADCx)
  - Digital to Analog Converters (DACx)
  - Ports (PORTx)
  - DMA Controller (DMAC)
  - IR Communication Module (IRCOM)
- The same event can be used by multiple peripherals for synchronized timing
- Advanced Features
  - Manual Event Generation from software (CPU)
  - Quadrature Decoding
  - Digital Filtering
- Functions in Active and Idle mode

# 9.2 Overview

The Event System is a set of features for inter-peripheral communication. It enables the possibility for a change of state in one peripheral to automatically trigger actions in one or more peripherals. What changes in a peripheral that will trigger actions in other peripherals are configurable by software. It is a simple, but powerful system as it allows for autonomous control of peripherals without any use of interrupts, CPU or DMA resources.

The indication of a change in a peripheral is referred to as an event, and is usually the same as the interrupt conditions for that peripheral. Events are passed between peripherals using a dedicated routing network called the Event Routing Network. Figure 9-1 on page 16 shows a basic block diagram of the Event System with the Event Routing Network and the peripherals to which it is connected. This highly flexible system can be used for simple routing of signals, pin functions or for sequencing of events.

The maximum latency is two CPU clock cycles from when an event is generated in one peripheral, until the actions are triggered in one or more other peripherals.

The Event System is functional in both Active and Idle modes.






Figure 9-1. Event system block diagram.

The Event Routing Network can directly connect together ADCs, DACs, Analog Comparators (ACx), I/O ports (PORTx), the Real-time Counter (RTC), Timer/Counters (T/C) and the IR Communication Module (IRCOM). Events can also be generated from software (CPU).

All events from all peripherals are always routed into the Event Routing Network. This consist of eight multiplexers where each can be configured in software to select which event to be routed into that event channel. All eight event channels are connected to the peripherals that can use events, and each of these peripherals can be configured to use events from one or more event channels to automatically trigger a software selectable action.

# 10. System Clock and Clock options

### 10.1 Features

- Fast start-up time
- · Safe run-time clock switching
- Internal Oscillators:
  - 32 MHz run-time calibrated RC oscillator
  - 2 MHz run-time calibrated RC oscillator
  - 32,768 kHz calibrated RC oscillator
  - 32 kHz Ultra Low Power (ULP) oscillator
- External clock options
  - 0.4 16 MHz Crystal Oscillator
  - 32.768 kHz Crystal Oscillator
  - External clock
- PLL with internal and external clock options with 2 to 31x multiplication
- Clock Prescalers with 2 to 2048x division
- Fast peripheral clock running at 2 and 4 times the CPU clock speed
- Automatic Run-Time Calibration of internal oscillators
- · Crystal Oscillator failure detection

### 10.2 Overview

XMEGA A3B has an advanced clock system, supporting a large number of clock sources. It incorporates both integrated oscillators, external crystal oscillators and resonators. A high frequency Phase Locked Loop (PLL) and clock prescalers can be controlled from software to generate a wide range of clock frequencies from the clock source input.

It is possible to switch between clock sources from software during run-time. After reset the device will always start up running from the 2 Mhz internal oscillator.

A calibration feature is available, and can be used for automatic run-time calibration of the internal 2 MHz and 32 MHz oscillators. This reduce frequency drift over voltage and temperature.

A Crystal Oscillator Failure Monitor can be enabled to issue a Non-Maskable Interrupt and switch to internal oscillator if the external oscillator fails. Figure 10-1 on page 18 shows the principal clock system in XMEGA A3B.






Figure 10-1. Clock system overview

Each clock source is briefly described in the following sub-sections.

# 10.3 Clock Options

### 10.3.1 32 kHz Ultra Low Power Internal Oscillator

The 32 kHz Ultra Low Power (ULP) Internal Oscillator is a very low power consumption clock source. It is used for the Watchdog Timer, Brown-Out Detection and as an asynchronous clock source for the Real Time Counter. This oscillator cannot be used as the system clock source, and it cannot be directly controlled from software.

### 10.3.2 32.768 kHz Calibrated Internal Oscillator

The 32.768 kHz Calibrated Internal Oscillator is a high accuracy clock source that can be used as the system clock source or as an asynchronous clock source for the Real Time Counter. It is calibrated during production to provide a default frequency which is close to its nominal frequency.

#### 10.3.3 32.768 kHz Crystal Oscillator

The 32.768 kHz Crystal Oscillator is a low power driver for an external watch crystal. It can be used as system clock source or as asynchronous clock source for the Real Time Counter.

#### 10.3.4 0.4 - 16 MHz Crystal Oscillator

The 0.4 - 16 MHz Crystal Oscillator is a driver intended for driving both external resonators and crystals ranging from 400 kHz to 16 MHz.

#### 10.3.5 2 MHz Run-time Calibrated Internal Oscillator

The 2 MHz Run-time Calibrated Internal Oscillator is a high frequency oscillator. It is calibrated during production to provide a default frequency which is close to its nominal frequency. The oscillator can use the 32.768 kHz Calibrated Internal Oscillator or the 32 kHz Crystal Oscillator as a source for calibrating the frequency run-time to compensate for temperature and voltage drift hereby optimizing the accuracy of the oscillator.

#### 10.3.6 32 MHz Run-time Calibrated Internal Oscillator

The 32 MHz Run-time Calibrated Internal Oscillator is a high frequency oscillator. It is calibrated during production to provide a default frequency which is close to its nominal frequency. The oscillator can use the 32.768 kHz Calibrated Internal Oscillator or the 32 kHz Crystal Oscillator as a source for calibrating the frequency run-time to compensate for temperature and voltage drift hereby optimizing the accuracy of the oscillator.

#### 10.3.7 **External Clock input**

The external clock input gives the possibility to connect a clock from an external source.

#### 10.3.8 PLL with Multiplication factor 2 - 31x

The PLL provides the possibility of multiplying a frequency by any number from 2 to 31. In combination with the prescalers, this gives a wide range of output frequencies from all clock sources.

# 11. Power Management and Sleep Modes

### 11.1 Features

- 5 sleep modes
  - Idle
  - Power-down
  - Power-save
  - Standby
  - Extended standby
- · Power Reduction registers to disable clocks to unused peripherals

### 11.2 Overview

The XMEGA A3B provides various sleep modes tailored to reduce power consumption to a minimum. All sleep modes are available and can be entered from Active mode. In Active mode the CPU is executing application code. The application code decides when and what sleep mode to enter. Interrupts from enabled peripherals and all enabled reset sources can restore the microcontroller from sleep to Active mode.

In addition, Power Reduction registers provide a method to stop the clock to individual peripherals from software. When this is done, the current state of the peripheral is frozen and there is no power consumption from that peripheral. This reduces the power consumption in Active mode and Idle sleep mode.

# 11.3 Sleep Modes

### 11.3.1 Idle Mode

In Idle mode the CPU and Non-Volatile Memory are stopped, but all peripherals including the Interrupt Controller, Event System and DMA Controller are kept running. Interrupt requests from all enabled interrupts will wake the device.

### 11.3.2 Power-down Mode

In Power-down mode all system clock sources, and the asynchronous Real Time Counter (RTC) clock source, are stopped. This allows operation of asynchronous modules only. The only interrupts that can wake up the MCU are the Two Wire Interface address match interrupts, and asynchronous port interrupts, e.g pin change.

### 11.3.3 Power-save Mode

Power-save mode is identical to Power-down, with one exception: If the RTC is enabled, it will keep running during sleep and the device can also wake up from RTC interrupts.

### 11.3.4 Standby Mode

Standby mode is identical to Power-down with the exception that all enabled system clock sources are kept running, while the CPU, Peripheral and RTC clocks are stopped. This reduces the wake-up time when external crystals or resonators are used.



#### 11.3.5 **Extended Standby Mode**

Extended Standby mode is identical to Power-save mode with the exception that all enabled system clock sources are kept running while the CPU and Peripheral clocks are stopped. This reduces the wake-up time when external crystals or resonators are used.

# 12. System Control and Reset

### 12.1 Features

- Multiple reset sources for safe operation and device reset
  - Power-On Reset
  - External Reset
  - Watchdog Reset

The Watchdog Timer runs from separate, dedicated oscillator

- Brown-Out Reset
  - Accurate, programmable Brown-Out levels
- JTAG Reset
- PDI reset
- Software reset
- · Asynchronous reset
- No running clock in the device is required for reset
- · Reset status register

## 12.2 Resetting the AVR

During reset, all I/O registers are set to their initial values. The SRAM content is not reset. Application execution starts from the Reset Vector. The instruction placed at the Reset Vector should be an Absolute Jump (JMP) instruction to the reset handling routine. By default the Reset Vector address is the lowest Flash program memory address, '0', but it is possible to move the Reset Vector to the first address in the Boot Section.

The I/O ports of the AVR are immediately tri-stated when a reset source goes active.

The reset functionality is asynchronous, so no running clock is required to reset the device.

After the device is reset, the reset source can be determined by the application by reading the Reset Status Register.

### 12.3 Reset Sources

### 12.3.1 Power-On Reset

The MCU is reset when the supply voltage VCC is below the Power-on Reset threshold voltage.

### 12.3.2 External Reset

The MCU is reset when a low level is present on the RESET pin.

# 12.3.3 Watchdog Reset

The MCU is reset when the Watchdog Timer period expires and the Watchdog Reset is enabled. The Watchdog Timer runs from a dedicated oscillator independent of the System Clock. For more details see "WDT - Watchdog Timer" on page 23.

### 12.3.4 Brown-Out Reset

The MCU is reset when the supply voltage VCC is below the Brown-Out Reset threshold voltage and the Brown-out Detector is enabled. The Brown-out threshold voltage is programmable.



### 12.3.5 JTAG reset

The MCU is reset as long as there is a logic one in the Reset Register in one of the scan chains of the JTAG system. Refer to IEEE 1149.1 (JTAG) Boundary-scan for details.

### 12.3.6 PDI reset

The MCU can be reset through the Program and Debug Interface (PDI).

### 12.3.7 Software reset

The MCU can be reset by the CPU writing to a special I/O register through a timed sequence.

# 12.4 WDT - Watchdog Timer

### 12.4.1 Features

- 11 selectable timeout periods, from 8 ms to 8s.
- Two operation modes
  - Standard mode
  - Window mode
- Runs from the 1 kHz output of the 32 kHz Ultra Low Power oscillator
- · Configuration lock to prevent unwanted changes

### 12.4.2 Overview

The XMEGA A3B has a Watchdog Timer (WDT). The WDT will run continuously when turned on and if the Watchdog Timer is not reset within a software configurable time-out period, the microcontroller will be reset. The Watchdog Reset (WDR) instruction must be run by software to reset the WDT, and prevents microcontroller reset.

The WDT has a Window mode. In this mode the WDR instruction must be run within a specified period called a window. Application software can set the minimum and maximum limits for this window. If the WDR instruction is not executed inside the window limits, the microcontroller will be reset.

A protection mechanism using a timed write sequence is implemented in order to prevent unwanted enabling, disabling or change of WDT settings.

For maximum safety, the WDT also has an Always-on mode. This mode is enabled by programming a fuse. In Always-on mode, application software can not disable the WDT.

# 13. Battery Backup System

### 13.1 Features

- Battery Backup voltage supply from dedicated V<sub>BAT</sub> power pin for:
  - One Ultra Low-power 32-bit Real Time Counter
  - One 32.768 kHz crystal oscillator with failure detection monitor
  - Two Backup Registers
- Typical power consumption of 500nA with Real Time Counter (RTC) running
- Automatic switching from main power to battery backup power at:
  - Brown-Out Detection (BOD) reset
- Automatic switching from battery backup power to main power:
  - Device reset after Brown-Out Reset (BOR) is released
  - Device reset after Power-On Reset (POR) and BOR is released

### 13.2 Overview

The AVR XMEGA family is already running in an ultra low leakage process with power-save current consumption below 2 µA with RTC, BOD and watchdog enabled. Still, for some applications where time keeping is important, the system would have one main battery or power source used for day to day tasks, and one backup battery power for the time keeping functionality. The Battery Backup System includes functionality that enable automatic power switching between main power and a battery backup power. Figure 13-1 on page 25 shows an overview of the system.

The Battery Backup Module support connection of a backup battery to the dedicated  $V_{BAT}$  power pin. This will ensure power to the 32-bit Real Time Counter, a 32.768 kHz crystal oscillator with failure detection monitor and two backup registers, when the main battery or power source is unavailable.

Upon main power loss the device will automatically detect this and the Battery Backup Module will switch to be powered from the  $V_{BAT}$  pin. After main power has been restored and both main POR and BOR are released, the Battery Backup Module will automatically switch back to be powered from main power again.

The 32-bit Real Time Counter (RTC) must be clocked from the 1 Hz output of a 32.768 kHz crystal oscillator connected between the TOSC1 and TOSC2 pins when running from  $V_{BAT}$ . For more details on the 32-bit RTC refer to the "RTC32 - 32-bit Real Time Counter" section in the XMEGA A Manual.



Power Power Watchdog w/ Main VCC **VBAT** switch independent supervisor power (BBPOD, **RCOSC** supervision BBBOD, BBPWR) XTAL1 OCD & Oscillator & Programming sleep Interface controller XTAL2 **AVR** CPU Level Failure TOSC1 **GPIO** Monitor Peripherals shifters / Isolation XOSC TOSC2 FLASH, Internal RTC EEPROM RAM & Fuses Backup Registers

Figure 13-1. Battery Backup Module and its power domain implementation

# 14. PMIC - Programmable Multi-level Interrupt Controller

#### 14.1 **Features**

- Separate interrupt vector for each interrupt
- · Short, predictable interrupt response time
- Programmable Multi-level Interrupt Controller
  - 3 programmable interrupt levels
  - Selectable priority scheme within low level interrupts (round-robin or fixed)
  - Non-Maskable Interrupts (NMI)
- Interrupt vectors can be moved to the start of the Boot Section

### 14.2 Overview

XMEGA A3B has a Programmable Multi-level Interrupt Controller (PMIC). All peripherals can define three different priority levels for interrupts; high, medium or low. Medium level interrupts may interrupt low level interrupt service routines. High level interrupts may interrupt both lowand medium level interrupt service routines. Low level interrupts have an optional round robin scheme to make sure all interrupts are serviced within a certain amount of time.

The built in oscillator failure detection mechanism can issue a Non-Maskable Interrupt (NMI).

# 14.3 Interrupt vectors

When an interrupt is serviced, the program counter will jump to the interrupt vector address. The interrupt vector is the sum of the peripheral's base interrupt address and the offset address for specific interrupts in each peripheral. The base addresses for the XMEGA A3B devices are shown in Table 14-1. Offset addresses for each interrupt available in the peripheral are described for each peripheral in the XMEGA A manual. For peripherals or modules that have only one interrupt, the interrupt vector is shown in Table 14-1. The program address is the word address.

**Table 14-1.** Reset and Interrupt Vectors

Program Address (Base Address)	Source	Interrupt Description
0x000	RESET	
0x002	OSCF_INT_vect	Crystal Oscillator Failure Interrupt vector (NMI)
0x004	PORTC_INT_base	Port C Interrupt base
800x0	PORTR_INT_base	Port R Interrupt base
0x00C	DMA_INT_base	DMA Controller Interrupt base
0x014	RTC32_INT_base	32-bit Real Time Counter Interrupt base
0x018	TWIC_INT_base	Two-Wire Interface on Port C Interrupt base
0x01C	TCC0_INT_base	Timer/Counter 0 on port C Interrupt base
0x028	TCC1_INT_base	Timer/Counter 1 on port C Interrupt base
0x030	SPIC_INT_vect	SPI on port C Interrupt vector
0x032	USARTC0_INT_base	USART 0 on port C Interrupt base
0x038	USARTC1_INT_base	USART 1 on port C Interrupt base
0x03E	AES_INT_vect	AES Interrupt vector



 Table 14-1.
 Reset and Interrupt Vectors (Continued)

Program Address (Base Address)	Source	Interrupt Description
0x040	NVM_INT_base	Non-Volatile Memory Interrupt base
0x044	PORTB_INT_base	Port B Interrupt base
0x048	ACB_INT_base	Analog Comparator on Port B Interrupt base
0x04E	ADCB_INT_base	Analog to Digital Converter on Port B Interrupt base
0x056	PORTE_INT_base	Port E Interrupt base
0x05A	TWIE_INT_base	Two-Wire Interface on Port E Interrupt base
0x05E	TCE0_INT_base	Timer/Counter 0 on port E Interrupt base
0x06A	TCE1_INT_base	Timer/Counter 1 on port E Interrupt base
0x074	USARTE0_INT_base	USART 0 on port E Interrupt base
0x080	PORTD_INT_base	Port D Interrupt base
0x084	PORTA_INT_base	Port A Interrupt base
0x088	ACA_INT_base	Analog Comparator on Port A Interrupt base
0x08E	ADCA_INT_base	Analog to Digital Converter on Port A Interrupt base
0x09A	TCD0_INT_base	Timer/Counter 0 on port D Interrupt base
0x0A6	TCD1_INT_base	Timer/Counter 1 on port D Interrupt base
0x0AE	SPID_INT_vector	SPI on port D Interrupt vector
0x0B0	USARTD0_INT_base	USART 0 on port D Interrupt base
0x0B6	USARTD1_INT_base	USART 1 on port D Interrupt base
0x0D0	PORTF_INT_base	Port F INT base
0x0D8	TCF0_INT_base	Timer/Counter 0 on port F Interrupt base
0x0EE	USARTF0_INT_base	USART 0 on port F Interrupt base

# 15. I/O Ports

### 15.1 Features

- · Selectable input and output configuration for each pin individually
- Flexible pin configuration through dedicated Pin Configuration Register
- Synchronous and/or asynchronous input sensing with port interrupts and events
  - Sense both edges
  - Sense rising edges
  - Sense falling edges
  - Sense low level
- · Asynchronous wake-up from all input sensing configurations
- Two port interrupts with flexible pin masking
- · Highly configurable output driver and pull settings:
  - Totem-pole
  - Pull-up/-down
  - Wired-AND
  - Wired-OR
  - Bus-keeper
  - Inverted I/O
- Optional Slew rate control
- . Configuration of multiple pins in a single operation
- Read-Modify-Write (RMW) support
- Toggle/clear/set registers for Output and Direction registers
- Clock output on port pin
- Event Channel 0 output on port pin 7
- . Mapping of port registers (virtual ports) into bit accessible I/O memory space

## 15.2 Overview

The XMEGA A3B devices have flexible General Purpose I/O Ports. A port consists of up to 8 pins, ranging from pin 0 to pin 7. The ports implement several functions, including synchronous/asynchronous input sensing, pin change interrupts and configurable output settings. All functions are individual per pin, but several pins may be configured in a single operation.


# 15.3 I/O configuration

All port pins (Pn) have programmable output configuration. In addition, all port pins have an inverted I/O function. For an input, this means inverting the signal between the port pin and the pin register. For an output, this means inverting the output signal between the port register and the port pin. The inverted I/O function can be used also when the pin is used for alternate functions. The port pins also have configurable slew rate limitation to reduce electromagnetic emission.




# 15.3.1 Push-pull

Figure 15-1. I/O configuration - Totem-pole




### 15.3.2 Pull-down

Figure 15-2. I/O configuration - Totem-pole with pull-down (on input)



# 15.3.3 Pull-up


Figure 15-3. I/O configuration - Totem-pole with pull-up (on input)



# 15.3.4 Bus-keeper

The bus-keeper's weak output produces the same logical level as the last output level. It acts as a pull-up if the last level was '1', and pull-down if the last level was '0'.

Figure 15-4. I/O configuration - Totem-pole with bus-keeper



# 15.3.5 Others

Figure 15-5. Output configuration - Wired-OR with optional pull-down





Figure 15-6. I/O configuration - Wired-AND with optional pull-up




# 15.4 Input sensing

- · Sense both edges
- Sense rising edges
- · Sense falling edges
- Sense low level

Input sensing is synchronous or asynchronous depending on the enabled clock for the ports, and the configuration is shown in Figure 15-7 on page 31.

Figure 15-7. Input sensing system overview



When a pin is configured with inverted I/O the pin value is inverted before the input sensing.

# 15.5 Port Interrupt

Each port has two interrupts with separate priority and interrupt vector. All pins on the port can be individually selected as source for each of the interrupts. The interrupts are then triggered according to the input sense configuration for each pin configured as source for the interrupt.

### 15.6 Alternate Port Functions

In addition to the input/output functions on all port pins, most pins have alternate functions. This means that other modules or peripherals connected to the port can use the port pins for their functions, such as communication or pulse-width modulation. "Pinout and Pin Functions" on page 50 shows which modules on peripherals that enables alternate functions on a pin, and what alternate functions that is available on a pin.

## 16. T/C - 16-bit Timer/Counter with PWM

### 16.1 Features

- Seven 16-bit Timer/Counters
  - Four Timer/Counters of type 0
  - Three Timer/Counters of type 1
- Four Compare or Capture (CC) Channels in Timer/Counter 0
- Two Compare or Capture (CC) Channels in Timer/Counter 1
- Double Buffered Timer Period Setting
- Double Buffered Compare or Capture Channels
- Waveform Generation:
  - Single Slope Pulse Width Modulation
  - Dual Slope Pulse Width Modulation
  - Frequency Generation
- Input Capture:
  - Input Capture with Noise Cancelling
  - Frequency capture
  - Pulse width capture
  - 32-bit input capture
- Event Counter with Direction Control
- Timer Overflow and Timer Error Interrupts and Events
- One Compare Match or Capture Interrupt and Event per CC Channel
- Supports DMA Operation
- Hi-Resolution Extension (Hi-Res)
- Advanced Waveform Extension (AWEX)

## 16.2 Overview

XMEGA A3B has seven Timer/Counters, four Timer/Counter 0 and three Timer/Counter 1. The difference between them is that Timer/Counter 0 has four Compare/Capture channels, while Timer/Counter 1 has two Compare/Capture channels.

The Timer/Counters (T/C) are 16-bit and can count any clock, event or external input in the microcontroller. A programmable prescaler is available to get a useful T/C resolution. Updates of Timer and Compare registers are double buffered to ensure glitch free operation. Single slope PWM, dual slope PWM and frequency generation waveforms can be generated using the Compare Channels.

Through the Event System, any input pin or event in the microcontroller can be used to trigger input capture, hence no dedicated pins are required for this. The input capture has a noise canceller to avoid incorrect capture of the T/C, and can be used to do frequency and pulse width measurements.

A wide range of interrupt or event sources are available, including T/C Overflow, Compare match and Capture for each Compare/Capture channel in the T/C.

PORTC, PORTD and PORTE each has one Timer/Counter 0 and one Timer/Counter1. PORTF has one Timer/Counter 0. Notation of these are TCC0 (Time/Counter C0), TCC1, TCD0, TCD1, TCE0, TCE1 and TCF0, respectively.






Figure 16-1. Overview of a Timer/Counter and closely related peripherals

The Hi-Resolution Extension can be enabled to increase the waveform generation resolution by 2 bits (4x). This is available for all Timer/Counters. See "Hi-Res - High Resolution Extension" on page 35 for more details.

The Advanced Waveform Extension can be enabled to provide extra and more advanced features for the Timer/Counter. This are only available for Timer/Counter 0. See "AWEX - Advanced Waveform Extension" on page 34 for more details.

# 17. AWEX - Advanced Waveform Extension

#### 17.1 **Features**

- Output with complementary output from each Capture channel
- Four Dead Time Insertion (DTI) Units, one for each Capture channel
- 8-bit DTI Resolution
- Separate High and Low Side Dead-Time Setting
- Double Buffered Dead-Time
- Event Controlled Fault Protection
- Single Channel Multiple Output Operation (for BLDC motor control)
- Double Buffered Pattern Generation

### 17.2 Overview

The Advanced Waveform Extension (AWEX) provides extra features to the Timer/Counter in Waveform Generation (WG) modes. The AWEX enables easy and safe implementation of for example, advanced motor control (AC, BLDC, SR, and Stepper) and power control applications.

Any WG output from a Timer/Counter 0 is split into a complimentary pair of outputs when any AWEX feature is enabled. These output pairs go through a Dead-Time Insertion (DTI) unit that enables generation of the non-inverted Low Side (LS) and inverted High Side (HS) of the WG output with dead time insertion between LS and HS switching. The DTI output will override the normal port value according to the port override setting. Optionally the final output can be inverted by using the invert I/O setting for the port pin.

The Pattern Generation unit can be used to generate a synchronized bit pattern on the port it is connected to. In addition, the waveform generator output from Compare Channel A can be distributed to, and override all port pins. When the Pattern Generator unit is enabled, the DTI unit is bypassed.

The Fault Protection unit is connected to the Event System. This enables any event to trigger a fault condition that will disable the AWEX output. Several event channels can be used to trigger fault on several different conditions.

The AWEX is available for TCC0. The notation is AWEXC.

# 18. Hi-Res - High Resolution Extension

### 18.1 Features

- Increases Waveform Generator resolution by 2-bits (4x)
- Supports Frequency, single- and dual-slope PWM operation
- . Supports the AWEX when this is enabled and used for the same Timer/Counter

## 18.2 Overview

The Hi-Resolution (Hi-Res) Extension is able to increase the resolution of the waveform generation output by a factor of 4. When enabled for a Timer/Counter, the Fast Peripheral clock running at four times the CPU clock speed will be as input to the Timer/Counter.

The High Resolution Extension can also be used when an AWEX is enabled and used with a Timer/Counter.

XMEGA A3B devices have four Hi-Res Extensions that each can be enabled for each Timer/Counters pair on PORTC, PORTD, PORTE and PORTF. The notation of these are HIRESC, HIRESD, HIRESE and HIRESF, respectively.

## 19. RTC32 - 32-bit Real-Time Counter

### 19.1 Features

- 32-bit resolution
- One 32-bit Compare register
- One 32-bit Period register
- · Clear Timer on overflow
- . Optional Interrupt/ Event on overflow and compare match
- Selectable clock reference
  - 1.024 kHz
  - 1 Hz
- Isolated V<sub>BAT</sub> power domain with dynamic switch over from/to V<sub>CC</sub> power domain'


### 19.1.1 Overview

The 32-bit Real Time Counter (RTC) is a 32-bit counter, counting reference clock cycles and giving an event and/or an interrupt request when it reaches a configurable compare and/or top value. The reference clock is generated from a high accuracy 32.768 kHz crystal, and the design is optimized for low power consumption. The RTC typically operate in low power sleep modes, keeping track of time and waking up the device at regular intervals.

The RTC input clock can be taken from a 1.024 kHz or 1 Hz prescaled output from the 32.768 kHz reference clock. The RTC will give a compare interrupt request and/or event when the counter value equals the Compare register value. The RTC will give an overflow interrupt request and/or event when the counter value equals the Period register value. Counter overflow will also reset the counter value to zero.

The 32-bit Real Time Counter (RTC) must be clocked from the 1 Hz output of a 32.768 kHz crystal oscillator connected between the TOSC1 and TOSC2 pins when running from  $V_{BAT}$ . For more details on the 32-bit RTC refer to the "32-bit Real Time Counter" section in the XMEGA A Manual.

Figure 19-1. Real Time Counter Overview





### 20. TWI - Two Wire Interface

#### 20.1 Features

- Two Identical TWI peripherals
- Simple yet Powerful and Flexible Communication Interface
- Both Master and Slave Operation Supported
- Device can Operate as Transmitter or Receiver
- 7-bit Address Space Allows up to 128 Different Slave Addresses
- Multi-master Arbitration Support
- Up to 400 kHz Data Transfer Speed
- Slew-rate Limited Output Drivers
- Noise Suppression Circuitry Rejects Spikes on Bus Lines
- Fully Programmable Slave Address with General Call Support
- Address Recognition Causes Wake-up when in Sleep Mode
- I<sup>2</sup>C and System Management Bus (SMBus) compatible

### 20.2 Overview

The Two-Wire Interface (TWI) is a bi-directional wired-AND bus with only two lines, the clock (SCL) line and the data (SDA) line. The protocol makes it possible to interconnect up to 128 individually addressable devices. Since it is a multi-master bus, one or more devices capable of taking control of the bus can be connected.

The only external hardware needed to implement the bus is a single pull-up resistor for each of the TWI bus lines. Mechanisms for resolving bus contention are inherent in the TWI protocol.

PORTC and PORTE, each has one TWI. Notation of these peripherals are TWIC, and TWIE, respectively.

# 21. SPI - Serial Peripheral Interface

### 21.1 Features

- Two Identical SPI peripherals
- Full-duplex, Three-wire Synchronous Data Transfer
- Master or Slave Operation
- LSB First or MSB First Data Transfer
- Seven Programmable Bit Rates
- End of Transmission Interrupt Flag
- Write Collision Flag Protection
- Wake-up from Idle Mode
- Double Speed (CK/2) Master SPI Mode

# 21.2 Overview

The Serial Peripheral Interface (SPI) allows high-speed full-duplex, synchronous data transfer between different devices. Devices can communicate using a master-slave scheme, and data is transferred both to and from the devices simultaneously.

PORTC and PORTD each has one SPI. Notation of these peripherals are SPIC and SPID, respectively.

# 22. USART

#### 22.1 Features

- Six Identical USART peripherals
- Full Duplex Operation (Independent Serial Receive and Transmit Registers)
- Asynchronous or Synchronous Operation
- Master or Slave Clocked Synchronous Operation
- High-resolution Arithmetic Baud Rate Generator
- Supports Serial Frames with 5, 6, 7, 8, or 9 Data Bits and 1 or 2 Stop Bits
- Odd or Even Parity Generation and Parity Check Supported by Hardware
- Data OverRun Detection
- Framing Error Detection
- . Noise Filtering Includes False Start Bit Detection and Digital Low Pass Filter
- Three Separate Interrupts on TX Complete, TX Data Register Empty and RX Complete
- Multi-processor Communication Mode
- Double Speed Asynchronous Communication Mode
- Master SPI mode for SPI communication
- · IrDA support through the IRCOM module

# 22.2 Overview

The Universal Synchronous and Asynchronous serial Receiver and Transmitter (USART) is a highly flexible serial communication module. The USART supports full duplex communication, and both asynchronous and clocked synchronous operation. The USART can also be set in Master SPI mode to be used for SPI communication.

Communication is frame based, and the frame format can be customized to support a wide range of standards. The USART is buffered in both direction, enabling continued data transmission without any delay between frames. There are separate interrupt vectors for receive and transmit complete, enabling fully interrupt driven communication. Frame error and buffer overflow are detected in hardware and indicated with separate status flags. Even or odd parity generation and parity check can also be enabled.

One USART can use the IRCOM module to support IrDA 1.4 physical compliant pulse modulation and demodulation for baud rates up to 115.2 kbps.

PORTC and PORTD each has two USARTs, while PORTE and PORTF each has one USART. Notation of these peripherals are USARTC0, USARTC1, USARTD0, USARTD1, USARTE0 and USARTF0, respectively.

# 23. IRCOM - IR Communication Module

#### 23.1 Features

- Pulse modulation/demodulation for infrared communication
- Compatible to IrDA 1.4 physical for baud rates up to 115.2 kbps
- Selectable pulse modulation scheme
  - 3/16 of baud rate period
  - Fixed pulse period, 8-bit programmable
  - Pulse modulation disabled
- · Built in filtering
- · Can be connected to and used by one USART at a time

# 23.2 Overview

XMEGA A3B contains an Infrared Communication Module (IRCOM) for IrDA communication with baud rates up to 115.2 kbps. This supports three modulation schemes: 3/16 of baud rate period, fixed programmable pulse time based on the Peripheral Clock speed, or pulse modulation disabled. There is one IRCOM available which can be connected to any USART to enable infrared pulse coding/decoding for that USART.

# 24. Crypto Engine

#### 24.1 Features

- Data Encryption Standard (DES) CPU instruction
- Advanced Encryption Standard (AES) Crypto module
- DES Instruction
  - Encryption and Decryption
  - Single-cycle DES instruction
  - Encryption/Decryption in 16 clock cycles per 8-byte block
- AES Crypto Module
  - Encryption and Decryption
  - Support 128-bit keys
  - Support XOR data load mode to the State memory for Cipher Block Chaining
  - Encryption/Decryption in 375 clock cycles per 16-byte block

#### 24.2 Overview

The Advanced Encryption Standard (AES) and Data Encryption Standard (DES) are two commonly used encryption standards. These are supported through an AES peripheral module and a DES CPU instruction. All communication interfaces and the CPU can optionally use AES and DES encrypted communication and data storage.

DES is supported by a DES instruction in the AVR XMEGA CPU. The 8-byte key and 8-byte data blocks must be loaded into the Register file, and then DES must be executed 16 times to encrypt/decrypt the data block.

The AES Crypto Module encrypts and decrypts 128-bit data blocks with the use of a 128-bit key. The key and data must be loaded into the key and state memory in the module before encryption/decryption is started. It takes 375 peripheral clock cycles before the encryption/decryption is done and decrypted/encrypted data can be read out, and an optional interrupt can be generated. The AES Crypto Module also has DMA support with transfer triggers when encryption/decryption is done and optional auto-start of encryption/decryption when the state memory is fully loaded.



# 25. ADC - 12-bit Analog to Digital Converter

#### 25.1 Features

- Two ADCs with 12-bit resolution
- 2 Msps sample rate for each ADC
- Signed and Unsigned conversions
- 4 result registers with individual input channel control for each ADC
- 8 single ended inputs for each ADC
- 8x4 differential inputs for each ADC
- 4 internal inputs:
  - Integrated Temperature Sensor
  - DAC Output
  - VCC voltage divided by 10
  - Bandgap voltage
- Software selectable gain of 2, 4, 8, 16, 32 or 64
- Software selectable resolution of 8- or 12-bit.
- Internal or External Reference selection
- Event triggered conversion for accurate timing
- DMA transfer of conversion results
- Interrupt/Event on compare result

#### 25.2 Overview

XMEGA A3B devices have two Analog to Digital Converters (ADC), see Figure 25-1 on page 43. The two ADC modules can be operated simultaneously, individually or synchronized.

The ADC converts analog voltages to digital values. The ADC has 12-bit resolution and is capable of converting up to 2 million samples per second. The input selection is flexible, and both single-ended and differential measurements can be done. For differential measurements an optional gain stage is available to increase the dynamic range. In addition several internal signal inputs are available. The ADC can provide both signed and unsigned results.

This is a pipeline ADC. A pipeline ADC consists of several consecutive stages, where each stage convert one part of the result. The pipeline design enables high sample rate at low clock speeds, and remove limitations on samples speed versus propagation delay. This also means that a new analog voltage can be sampled and a new ADC measurement started while other ADC measurements are ongoing.


ADC measurements can either be started by application software or an incoming event from another peripheral in the device. Four different result registers with individual input selection (MUX selection) are provided to make it easier for the application to keep track of the data. Each result register and MUX selection pair is referred to as an ADC Channel. It is possible to use DMA to move ADC results directly to memory or peripherals when conversions are done.

Both internal and external analog reference voltages can be used. An accurate internal 1.0V reference is available.

An integrated temperature sensor is available and the output from this can be measured with the ADC. The output from the DAC, VCC/10 and the Bandgap voltage can also be measured by the ADC.



Figure 25-1. ADC overview



Each ADC has four MUX selection registers with a corresponding result register. This means that four channels can be sampled within 1.5 µs without any intervention by the application other than starting the conversion. The results will be available in the result registers.

The ADC may be configured for 8- or 12-bit result, reducing the minimum conversion time (propagation delay) from 3.5  $\mu$ s for 12-bit to 2.5  $\mu$ s for 8-bit result.

ADC conversion results are provided left- or right adjusted with optional '1' or '0' padding. This eases calculation when the result is represented as a signed integer (signed 16-bit number).

PORTA and PORTB each have one ADC. Notation of these peripherals are ADCA and ADCB, respectively.

# 26. DAC - 12-bit Digital to Analog Converter

### 26.1 Features


- One DAC with 12-bit resolution
- Up to 1 Msps conversion rate for each DAC
- Flexible conversion range
- Multiple trigger sources
- 1 continuous output or 2 Sample and Hold (S/H) outputs for each DAC
- · Built-in offset and gain calibration
- · High drive capabilities
- Low Power Mode

#### 26.2 Overview

The XMEGA A3B devices features one two-channel, 12-bit, 1 Msps DACs with built-in offset and gain calibration, see Figure 26-1 on page 44.

A DAC converts a digital value into an analog signal. The DAC may use an internal 1.0 voltage as the upper limit for conversion, but it is also possible to use the supply voltage or any applied voltage in-between. The external reference input is shared with the ADC reference input.

Figure 26-1. DAC overview



The DAC has one continuous output with high drive capabilities for both resistive and capacitive loads. It is also possible to split the continuous time channel into two Sample and Hold (S/H) channels, each with separate data conversion registers.

A DAC conversion may be started from the application software by writing the data conversion registers. The DAC can also be configured to do conversions triggered by the Event System to have regular timing, independent of the application software. DMA may be used for transferring data from memory locations to DAC data registers.

The DAC has a built-in calibration system to reduce offset and gain error when loading with a calibration value from software.

PORTB has one DAC. Notation of this is DACB.



# 27. AC - Analog Comparator

### 27.1 Features

- Four Analog Comparators
- Selectable Power vs. Speed
- · Selectable hysteresis
  - 0, 20 mV, 50 mV
- Analog Comparator output available on pin
- Flexible Input Selection
  - All pins on the port
  - Output from the DAC
  - Bandgap reference voltage.
  - Voltage scaler that can perform a 64-level scaling of the internal VCC voltage.
- · Interrupt and event generation on
  - Rising edge
  - Falling edge
  - Toggle
- · Window function interrupt and event generation on
  - Signal above window
  - Signal inside window
  - Signal below window

#### 27.2 Overview

XMEGA A3B features four Analog Comparators (AC). An Analog Comparator compares two voltages, and the output indicates which input is largest. The Analog Comparator may be configured to give interrupt requests and/or events upon several different combinations of input change.

Both hysteresis and propagation delays may be adjusted in order to find the optimal operation for each application.

A wide range of input selection is available, both external pins and several internal signals can be used.

The Analog Comparators are always grouped in pairs (AC0 and AC1) on each analog port. They have identical behavior but separate control registers.

Optionally, the state of the comparator is directly available on a pin.

PORTA and PORTB each have one AC pair. Notations are ACA and ACB, respectively.






Figure 27-1. Analog comparator overview

# 27.3 Input Selection


The Analog comparators have a very flexible input selection and the two comparators grouped in a pair may be used to realize a window function. One pair of analog comparators is shown in Figure 27-1 on page 46.

- Input selection from pin
  - Pin 0, 1, 2, 3, 4, 5, 6 selectable to positive input of analog comparator
  - Pin 0, 1, 3, 5, 7 selectable to negative input of analog comparator
- · Internal signals available on positive analog comparator inputs
  - Output from 12-bit DAC
- Internal signals available on negative analog comparator inputs
  - 64-level scaler of the VCC, available on negative analog comparator input
  - Bandgap voltage reference
  - Output from 12-bit DAC

### 27.4 Window Function

The window function is realized by connecting the external inputs of the two analog comparators in a pair as shown in Figure 27-2.

Figure 27-2. Analog comparator window function



# 28. OCD - On-chip Debug

#### 28.1 Features

- Complete Program Flow Control
  - Go, Stop, Reset, Step into, Step over, Step out, Run-to-Cursor
- Debugging on C and high-level language source code level
- Debugging on Assembler and disassembler level
- 1 dedicated program address or source level breakpoint for AVR Studio / debugger
- 4 Hardware Breakpoints
- Unlimited Number of User Program Breakpoints
- Unlimited Number of User Data Breakpoints, with break on:
  - Data location read, write or both read and write
  - Data location content equal or not equal to a value
  - Data location content is greater or less than a value
  - Data location content is within or outside a range
  - Bits of a data location are equal or not equal to a value
- Non-Intrusive Operation
  - No hardware or software resources in the device are used
- High Speed Operation
  - No limitation on debug/programming clock frequency versus system clock frequency

#### 28.2 Overview

The XMEGA A3B has a powerful On-Chip Debug (OCD) system that - in combination with Atmel's development tools - provides all the necessary functions to debug an application. It has support for program and data breakpoints, and can debug an application from C and high level language source code level, as well as assembler and disassembler level. It has full Non-Intrusive Operation and no hardware or software resources in the device are used. The ODC system is accessed through an external debugging tool which connects to the JTAG or PDI physical interfaces. Refer to "Program and Debug Interfaces" on page 49.



# 29. Program and Debug Interfaces

### 29.1 Features

- PDI Program and Debug Interface (Atmel proprietary 2-pin interface)
- JTAG Interface (IEEE std. 1149.1 compliant)
- Boundary-scan capabilities according to the IEEE Std. 1149.1 (JTAG)
- · Access to the OCD system
- . Programming of Flash, EEPROM, Fuses and Lock Bits

#### 29.2 Overview

The programming and debug facilities are accessed through the JTAG and PDI physical interfaces. The PDI physical uses one dedicated pin together with the Reset pin, and no general purpose pins are used. JTAG uses four general purpose pins on PORTB.

# 29.3 JTAG interface

The JTAG physical layer handles the basic low-level serial communication over four I/O lines named TMS, TCK, TDI, and TDO. It complies to the IEEE Std. 1149.1 for test access port and boundary scan.

# 29.4 PDI - Program and Debug Interface

The PDI is an Atmel proprietary protocol for communication between the microcontroller and Atmel's development tools.

# 30. Pinout and Pin Functions

The pinout of XMEGA A3B is shown in "Pinout/Block Diagram" on page 3. In addition to general I/O functionality, each pin may have several functions. This will depend on which peripheral is enabled and connected to the actual pin. Only one of the alternate pin functions can be used at time.

# 30.1 Alternate Pin Function Description

The tables below shows the notation for all pin functions available and describes its function.

# 30.1.1 Operation/Power Supply

VCC Digital supply voltage
AVCC Analog supply voltage

VBAT Battery Backup Module supply voltage

GND Ground

#### 30.1.2 Port Interrupt functions

SYNC Port pin with full synchronous and limited asynchronous interrupt function

ASYNC Port pin with full synchronous and full asynchronous interrupt function

### 30.1.3 Analog functions

ACn Analog Comparator input pin n
AC0OUT Analog Comparator 0 Output

ADCn Analog to Digital Converter input pin n

DACn Digital to Analog Converter output pin n

AREF Analog Reference input pin

#### 30.1.4 Timer/Counter and AWEX functions

OCnx Output Compare Channel x for Timer/Counter n

OCnx

Inverted Output Compare Channel x for Timer/Counter n

OCnxLS

Output Compare Channel x Low Side for Timer/Counter n

OCnxHS

Output Compare Channel x High Side for Timer/Counter n

# 30.1.5 Communication functions

SCL Serial Clock for TWI SDA Serial Data for TWI

SCLIN Serial Clock In for TWI when external driver interface is enabled SCLOUT Serial Clock Out for TWI when external driver interface is enabled



SDAIN Serial Data In for TWI when external driver interface is enabled

SDAOUT Serial Data Out for TWI when external driver interface is enabled

XCKn Transfer Clock for USART n

RXDn Receiver Data for USART n

TXDn Transmitter Data for USART n

SIave Select for SPI

MOSI Master Out Slave In for SPI
MISO Master In Slave Out for SPI

SCK Serial Clock for SPI

# 30.1.6 Oscillators, Clock and Event

TOSCn Timer Oscillator pin n

XTALn Input/Output for inverting Oscillator pin n

CLKOUT Peripheral Clock Output
EVOUT Event Channel 0 Output

# 30.1.7 Debug/System functions

RESET Reset pin

PDI\_CLK Program and Debug Interface Clock pin
PDI\_DATA Program and Debug Interface Data pin

TCK JTAG Test Clock

TDI JTAG Test Data In

TDO JTAG Test Data Out

TMS JTAG Test Mode Select



# 30.2 Alternate Pin Functions

The tables below show the primary/default function for each pin on a port in the first column, the pin number in the second column, and then all alternate pin functions in the remaining columns. The head row shows what peripheral that enable and use the alternate pin functions.

Table 30-1. Port A - Alternate functions

PORT A	PIN#	INTERRUPT	ADCA POS	ADCA NEG	ADCA GAINPOS	ADCA GAINNEG	ACA POS	ACA NEG	ACA OUT	REFA
GND	60									
AVCC	61									
PA0	62	SYNC	ADC0	ADC0	ADC0		AC0	AC0		AREF
PA1	63	SYNC	ADC1	ADC1	ADC1		AC1	AC1		
PA2	64	SYNC/ASYNC	ADC2	ADC2	ADC2		AC2			
PA3	1	SYNC	ADC3	ADC3	ADC3		AC3	AC3		
PA4	2	SYNC	ADC4		ADC4	ADC4	AC4			
PA5	3	SYNC	ADC5		ADC5	ADC5	AC5	AC5		
PA6	4	SYNC	ADC6		ADC6	ADC6	AC6			
PA7	5	SYNC	ADC7		ADC7	ADC7		AC7	AC0OUT	

**Table 30-2.** Port B - Alternate functions

PORT B	PIN#	INTERRUPT	ADCB POS	ADCB NEG	ADCB GAINPOS	ADCB GAINNEG	ACB POS	ACB NEG	ACB OUT	DACB	REFB	JTAG
PB0	6	SYNC	ADC0	ADC0	ADC0		AC0	AC0			AREF	
PB1	7	SYNC	ADC1	ADC1	ADC1		AC1	AC1				
PB2	8	SYNC/ASYNC	ADC2	ADC2	ADC2		AC2			DAC0		
PB3	9	SYNC	ADC3	ADC3	ADC3		AC3	AC3		DAC1		
PB4	10	SYNC	ADC4		ADC4	ADC4	AC4					TMS
PB5	11	SYNC	ADC5		ADC5	ADC5	AC5	AC5				TDI
PB6	12	SYNC	ADC6		ADC6	ADC6	AC6					TCK
PB7	13	SYNC	ADC7		ADC7	ADC7		AC7	AC0OUT			TDO

Table 30-3. Port C - Alternate functions

PORT C	PIN#	INTERRUPT	TCC0	AWEXC	TCC1	USARTC0	USARTC1	SPIC	TWIC	CLOCKOU T	EVENTOUT
GND	14										
vcc	15										
PC0	16	SYNC	OC0A	OC0ALS					SDA/SDA_IN		
PC1	17	SYNC	OC0B	OC0AHS		XCK0			SCL/SCL_IN		
PC2	18	SYNC/ASYNC	OC0C	OC0BLS		RXD0			SDA_OUT		
PC3	19	SYNC	OC0D	OC0BHS		TXD0			SCL_OUT		
PC4	20	SYNC		OC0CLS	OC1A			SS			

 Table 30-3.
 Port C - Alternate functions (Continued)

PORT C	PIN#	INTERRUPT	TCC0	AWEXC	TCC1	USARTC0	USARTC1	SPIC	TWIC	CLOCKOU T	EVENTOUT
PC5	21	SYNC		OC0CHS	OC1B		XCK1	MOSI			
PC6	22	SYNC		OC0DLS			RXD1	MISO			
PC7	23	SYNC		OC0DHS			TXD1	SCK		CLKOUT	EVOUT

### **Table 30-4.** Port D - Alternate functions

PORT D	PIN#	INTERRUPT	TCD0	TCD1	USARTD0	USARTD1	SPID	CLOCKOUT	EVENTOUT
GND	24								
vcc	25								
PD0	26	SYNC	OC0A						
PD1	27	SYNC	OC0B		XCK0				
PD2	28	SYNC/ASYNC	OC0C		RXD0				
PD3	29	SYNC	OC0D		TXD0				
PD4	30	SYNC		OC1A			SS		
PD5	31	SYNC		OC1B		XCK1	MOSI		
PD6	32	SYNC				RXD1	MISO		
PD7	33	SYNC				TXD1	SCK	CLKOUT	EVOUT

# Table 30-5. Port E - Alternate functions

PORT E	PIN#	INTERRUPT	TCE0	TCE1	USARTE0	TWIE
GND	34					
vcc	35					
PE0	36	SYNC	OC0A			SDA/SDA_IN
PE1	37	SYNC	OC0B		XCK0	SCL/SCL_IN
PE2	38	SYNC/ASYNC	OC0C		RXD0	SDA_OUT
PE3	39	SYNC	OC0D		TXD0	SCL_OUT
PE4	40	SYNC		OC1A		
PE5	41	SYNC		OC1B		
TOSC2	42					
TOSC1	43					

# **Table 30-6.** Port F - Alternate functions

PORT F	PIN#	INTERRUPT	TCF0	USARTF0
GND	44			
vcc	45			
PF0	46	SYNC	OC0A	
PF1	47	SYNC	OC0B	хско
PF2	48	SYNC/ASYNC	OC0C	RXD0
PF3	49	SYNC	OC0D	TXD0
PF4	50	SYNC	OC0A	
VBAT	51			

**Table 30-6.** Port F - Alternate functions (Continued)

PORT F	PIN#	INTERRUPT	TCF0	USARTF0
GND	52	SYNC		
vcc	53	SYNC		
PF6	54			
PF7	55			

Table 30-7. Port R- Alternate functions

PORT R	PIN#	INTERRUPT	PDI	XTAL
PDI	56		PDI_DATA	
RESET	57		PDI_CLK	
PRO	58	SYNC		XTAL2
PR1	59	SYNC		XTAL1

Table 30-8. ATxmega256A3B Boundary Scan Order

Bit Number	Signal Name	Module
149	PQ3.Bidir	
148	PQ3.Control	
147	PQ2.Bidir	
146	PQ2.Control	DODT O
145	PQ1.Bidir	PORT Q
144	PQ1.Control	
143	PQ0.Bidir	
142	PQ0.Control	
141	PK7.Bidir	
140	PK7.Control	
139	PK6.Bidir	
138	PK6.Control	
137	PK5.Bidir	
136	PK5.Control	
135	PK4.Bidir	
134	PK4.Control	PORT K
133	PK3.Bidir	PORTK
132	PK3.Control	
131	PK2.Bidir	
130	PK2.Control	
129	PK1.Bidir	
128	PK1.Control	
127	PK0.Bidir	
126	PK0.Control	

Bit Number	Cianal Nama	Madula
	Signal Name	Module
125	PJ7.Bidir	
124	PJ7.Control	
123	PJ6.Bidir	
122 121	PJ6.Control PJ5.Bidir	
120	PJ5.Control	
119	PJ4.Bidir	
118	PJ4.Control	
117	PJ3.Bidir	PORT J
116	PJ3.Control	
115	PJ2.Bidir	
114	PJ2.Control	
113	PJ1.Bidir	
112	PJ1.Control	
111	PJ0.Bidir	
110	PJ0.Control	
109	PH7.Bidir	
108	PH7.Control	
107	PH6.Bidir	
106	PH6.Control	
105 104	PH5.Bidir PH5.Control	
103	PH5.Control PH4.Bidir	
102	PH4.Control	
101	PH3.Bidir	PORT H
100	PH3.Control	
99	PH2.Bidir	
98	PH2.Control	
97	PH1.Bidir	
96	PH1.Control	
95	PH0.Bidir	
94	PH0.Control	
93	PF7.Bidir	
92	PF7.Control	
91	PF6.Bidir	
90	PF6.Control	
89 88	PF5.Bidir PF5.Control	
87	PF4.Bidir	
86	PF4.Control	
85	PF3.Bidir	PORT F
84	PF3.Control	
83	PF2.Bidir	
82	PF2.Control	
81	PF1.Bidir	
80	PF1.Control	
79	PF0.Bidir	
78	PF0.Control	
77	PE7.Bidir	
76	PE7.Control	
75	PE6.Bidir	
74	PE6.Control	
73 72	PE5.Bidir PE5.Control	
71	PE3.Control PE4.Bidir	
70	PE4.Control	
69	PE3.Bidir	PORT E
68	PE3.Control	
67	PE2.Bidir	
66	PE2.Control	
65	PE1.Bidir	
64	PE1.Control	
63	PE0.Bidir	
62	PE0.Control	



Bit Number	Signal Name	Module
	PD7.Bidir	
61 60	PD7.Bidii PD7.Control	-
59	PD6.Bidir	1
58	PD6.Control	1
57	PD5.Bidir	†
56	PD5.Control	1
55	PD4.Bidir	1
54	PD4.Control	
53	PD3.Bidir	PORT D
52	PD3.Control	]
51	PD2.Bidir	]
50	PD2.Control	]
49	PD1.Bidir	
48	PD1.Control	
47	PD0.Bidir	
46	PD0.Control	
45	PC7.Bidir	
44	PC7.Control	
43	PC6.Bidir	
42	PC6.Control	_
41	PC5.Bidir	_
40	PC5.Control	
39	PC4.Bidir	
38	PC4.Control	PORT C
37	PC3.Bidir	
36	PC3.Control	4
35	PC2.Bidir	4
34	PC2.Control	-
33	PC1.Bidir	-
32 31	PC1.Control PC0.Bidir	-
30	PC0.Control	-
29	PB3.Bidir	
28	PB3.Control	†
27	PB2.Bidir	†
26	PB2.Control	1
25	PB1.Bidir	PORT B
24	PB1.Control	
23	PB0.Bidir	
22	PB0.Control	]
21	PA7.Bidir	
20	PA7.Control	
19	PA6.Bidir	_
18	PA6.Control	_
17	PA5.Bidir	_
16	PA5.Control	
15	PA4.Bidir	_
14	PA4.Control	PORT A
13	PA3.Bidir	
12	PA3.Control	-
11	PA2.Bidir	4
10	PA2.Control	-
9	PA1.Bidir	-
8	PA1.Control	-
7	PA0.Bidir	-
6 5	PA0.Control	
4	PR1.Bidir	1
3	PR1.Control PR0.Bidir	PORT R
2	PRO.Bidir PRO.Control	1
1	RESET.Observe_Only	RESET
0	PDI_DATA.Observe_Only	PDI Data
_ ~	1 DI_D/(1/1.Ob3CiVC_Oilly	i Di Dala



# 31. Peripheral Module Address Map

The address maps show the base address for each peripheral and module in XMEGA A3B. For complete register description and summary for each peripheral module, refer to the XMEGA A Manual.

	i e	
Base Address	Name	Description
0x0000	GPIO	General Purpose IO Registers
0x0010	VPORT0	Virtual Port 0
0x0014	VPORT1	Virtual Port 1
0x0018	VPORT2	Virtual Port 2
0x001C	VPORT3	Virtual Port 2
0x0030	CPU	CPU
0x0040	CLK	Clock Control
0x0048	SLEEP	Sleep Controller
0x0050	OSC	Oscillator Control
0x0060	DFLLRC32M	DFLL for the 32 MHz Internal RC Oscillator
0x0068	DFLLRC2M	DFLL for the 2 MHz RC Oscillator
0x0070	PR	Power Reduction
0x0078	RST	Reset Controller
0x0080	WDT	Watch-Dog Timer
0x0090	MCU	MCU Control
0x00A0	PMIC	Programmable Multilevel Interrupt Controller
0x00B0	PORTCFG	Port Configuration
0x00C0	AES	AES Module
0x00F0	VBAT	VBAT Battery Backup Module
0x0100	DMA	DMA Controller
0x0180	EVSYS	Event System
0x01C0	NVM	Non Volatile Memory (NVM) Controller
0x0200	ADCA	Analog to Digital Converter on port A
0x0240	ADCB	Analog to Digital Converter on port B
0x0320	DACB	Digital to Analog Converter on port B
0x0380	ACA	Analog Comparator pair on port A
0x0390	ACB	Analog Comparator pair on port B
0x0420	RTC32	32-bit Real Time Counter
0x0480	TWIC	Two Wire Interface on port C
0x04A0	TWIE	Two Wire Interface on port E
0x0600	PORTA	Port A
0x0620	PORTB	Port B
0x0640	PORTC	Port C
0x0660 0x0680	PORTD PORTE	Port D Port E
0x06A0	PORTE	Port F
0x07E0	PORTR	Port R
0x0800	TCC0	Timer/Counter 0 on port C
0x0840	TCC1	Timer/Counter 1 on port C
0x0880	AWEXC	Advanced Waveform Extension on port C
0x0890	HIRESC	High Resolution Extension on port C
0x08A0	USARTC0	USART 0 on port C
0x08B0	USARTC1	USART 1 on port C
0x08C0	SPIC	Serial Peripheral Interface on port C
0x08F8	IRCOM	Infrared Communication Module
0x0900	TCD0	Timer/Counter 0 on port D
0x0940	TCD1	Timer/Counter 1 on port D
0x0990	HIRESD	High Resolution Extension on port D
0x09A0	USARTD0	USART 0 on port D
0x09B0	USARTD1	USART 1 on port D
0x09C0	SPID	Serial Peripheral Interface on port D
0x0A00	TCE0	Timer/Counter 0 on port E
0x0A40	TCE1	Timer/Counter 1 on port E
0x0A80	AWEXE	Advanced Waveform Extension on port E
0x0A90	HIRESE	High Resolution Extension on port E
0x0AA0	USARTE0	USART 0 on port E
0x0B00	TCF0	Timer/Counter 0 on port F
0x0B90	HIRESF	High Resolution Extension on port F
0x0BA0	USARTF0	USART 0 on port F



# 32. Instruction Set Summary

Mnemonics	Operands	Description	Opera	ation		Flags	#Clocks
		Arithmeti	c and Logic Instructions				
ADD	Rd, Rr	Add without Carry	Rd	<b>←</b>	Rd + Rr	Z,C,N,V,S,H	1
ADC	Rd, Rr	Add with Carry	Rd	<b>←</b>	Rd + Rr + C	Z,C,N,V,S,H	1
ADIW	Rd, K	Add Immediate to Word	Rd	<b>←</b>	Rd + 1:Rd + K	Z,C,N,V,S	2
SUB	Rd, Rr	Subtract without Carry	Rd	<b>←</b>	Rd - Rr	Z,C,N,V,S,H	1
SUBI	Rd, K	Subtract Immediate	Rd	<b>←</b>	Rd - K	Z,C,N,V,S,H	1
SBC	Rd, Rr	Subtract with Carry	Rd	←	Rd - Rr - C	Z,C,N,V,S,H	1
SBCI	Rd, K	Subtract Immediate with Carry	Rd	←	Rd - K - C	Z,C,N,V,S,H	1
SBIW	Rd, K	Subtract Immediate from Word	Rd + 1:Rd	←	Rd + 1:Rd - K	Z,C,N,V,S	2
AND	Rd, Rr	Logical AND	Rd	←	Rd • Rr	Z,N,V,S	1
ANDI	Rd, K	Logical AND with Immediate	Rd	←	Rd • K	Z,N,V,S	1
OR	Rd, Rr	Logical OR	Rd	←	Rd v Rr	Z,N,V,S	1
ORI	Rd, K	Logical OR with Immediate	Rd	←	Rd v K	Z,N,V,S	1
EOR	Rd, Rr	Exclusive OR	Rd	<b>←</b>	Rd ⊕ Rr	Z,N,V,S	1
COM	Rd	One's Complement	Rd	←	\$FF - Rd	Z,C,N,V,S	1
NEG	Rd	Two's Complement	Rd	<b>←</b>	\$00 - Rd	Z,C,N,V,S,H	1
SBR	Rd,K	Set Bit(s) in Register	Rd	<b>←</b>	Rd v K	Z,N,V,S	1
CBR	Rd,K	Clear Bit(s) in Register	Rd	<b>←</b>	Rd • (\$FFh - K)	Z,N,V,S	1
INC	Rd	Increment	Rd	←	Rd + 1	Z,N,V,S	1
DEC	Rd	Decrement	Rd	←	Rd - 1	Z,N,V,S	1
TST	Rd	Test for Zero or Minus	Rd	←	Rd • Rd	Z,N,V,S	1
CLR	Rd	Clear Register	Rd	←	$Rd \oplus Rd$	Z,N,V,S	1
SER	Rd	Set Register	Rd	←	\$FF	None	1
MUL	Rd,Rr	Multiply Unsigned	R1:R0	<b>←</b>	Rd x Rr (UU)	Z,C	2
MULS	Rd,Rr	Multiply Signed	R1:R0	<b>←</b>	Rd x Rr (SS)	Z,C	2
MULSU	Rd,Rr	Multiply Signed with Unsigned	R1:R0	<b>←</b>	Rd x Rr (SU)	Z,C	2
FMUL	Rd,Rr	Fractional Multiply Unsigned	R1:R0	<b>←</b>	Rd x Rr<<1 (UU)	Z,C	2
FMULS	Rd,Rr	Fractional Multiply Signed	R1:R0	<b>←</b>	Rd x Rr<<1 (SS)	Z,C	2
FMULSU	Rd,Rr	Fractional Multiply Signed with Unsigned	R1:R0	<b>←</b>	Rd x Rr<<1 (SU)	Z,C	2
DES	K	Data Encryption	if (H = 0) then R15:R0 else if (H = 1) then R15:R0	<b>←</b>	Encrypt(R15:R0, K) Decrypt(R15:R0, K)		1/2
		Br	anch Instructions				
RJMP	k	Relative Jump	PC	←	PC + k + 1	None	2
IJMP		Indirect Jump to (Z)	PC(15:0) PC(21:16)	<b>←</b>	Z, 0	None	2
EIJMP		Extended Indirect Jump to (Z)	PC(15:0) PC(21:16)	<b>←</b>	Z, EIND	None	2
JMP	k	Jump	PC	<b>←</b>	k	None	3
RCALL	k	Relative Call Subroutine	PC	<b>←</b>	PC + k + 1	None	2/3(1)
ICALL		Indirect Call to (Z)	PC(15:0) PC(21:16)	<b>←</b>	Z, 0	None	2/3 <sup>(1)</sup>
EICALL		Extended Indirect Call to (Z)	PC(15:0) PC(21:16)	<b>←</b>	Z, EIND	None	3 <sup>(1)</sup>



Mnemonics	Operands	Description	Opera	ation		Flags	#Clocks
CALL	k	call Subroutine	PC	<b>←</b>	k	None	3 / 4 <sup>(1)</sup>
RET		Subroutine Return	PC	<b>←</b>	STACK	None	4 / 5 <sup>(1)</sup>
RETI		Interrupt Return	PC	<b>←</b>	STACK	1	4 / 5 <sup>(1)</sup>
CPSE	Rd,Rr	Compare, Skip if Equal	if (Rd = Rr) PC	<b>←</b>	PC + 2 or 3	None	1/2/3
СР	Rd,Rr	Compare	Rd - Rr			Z,C,N,V,S,H	1
CPC	Rd,Rr	Compare with Carry	Rd - Rr - C			Z,C,N,V,S,H	1
CPI	Rd,K	Compare with Immediate	Rd - K			Z,C,N,V,S,H	1
SBRC	Rr, b	Skip if Bit in Register Cleared	if (Rr(b) = 0) PC	<b>←</b>	PC + 2 or 3	None	1/2/3
SBRS	Rr, b	Skip if Bit in Register Set	if (Rr(b) = 1) PC	<b>←</b>	PC + 2 or 3	None	1/2/3
SBIC	A, b	Skip if Bit in I/O Register Cleared	if (I/O(A,b) = 0) PC	<b>←</b>	PC + 2 or 3	None	2/3/4
SBIS	A, b	Skip if Bit in I/O Register Set	If (I/O(A,b) =1) PC	<b>←</b>	PC + 2 or 3	None	2/3/4
BRBS	s, k	Branch if Status Flag Set	if (SREG(s) = 1) then PC	<b>←</b>	PC + k + 1	None	1/2
BRBC	s, k	Branch if Status Flag Cleared	if (SREG(s) = 0) then PC	<b>←</b>	PC + k + 1	None	1/2
BREQ	k	Branch if Equal	if (Z = 1) then PC	<b>←</b>	PC + k + 1	None	1/2
BRNE	k	Branch if Not Equal	if (Z = 0) then PC	<b>←</b>	PC + k + 1	None	1/2
BRCS	k	Branch if Carry Set	if (C = 1) then PC	<b>←</b>	PC + k + 1	None	1/2
BRCC	k	Branch if Carry Cleared	if (C = 0) then PC	<b>←</b>	PC + k + 1	None	1/2
BRSH	k	Branch if Same or Higher	if (C = 0) then PC	<b>←</b>	PC + k + 1	None	1/2
BRLO	k	Branch if Lower	if (C = 1) then PC	<b>←</b>	PC + k + 1	None	1/2
BRMI	k	Branch if Minus	if (N = 1) then PC	<b>←</b>	PC + k + 1	None	1/2
BRPL	k	Branch if Plus	if (N = 0) then PC	<b>←</b>	PC + k + 1	None	1/2
BRGE	k	Branch if Greater or Equal, Signed	if (N ⊕ V= 0) then PC	<b>←</b>	PC + k + 1	None	1/2
BRLT	k	Branch if Less Than, Signed	if (N ⊕ V= 1) then PC	<b>←</b>	PC + k + 1	None	1/2
BRHS	k	Branch if Half Carry Flag Set	if (H = 1) then PC	<b>←</b>	PC + k + 1	None	1/2
BRHC	k	Branch if Half Carry Flag Cleared	if (H = 0) then PC	<b>←</b>	PC + k + 1	None	1/2
BRTS	k	Branch if T Flag Set	if (T = 1) then PC	<b>←</b>	PC + k + 1	None	1/2
BRTC	k	Branch if T Flag Cleared	if (T = 0) then PC	<b>←</b>	PC + k + 1	None	1/2
BRVS	k	Branch if Overflow Flag is Set	if (V = 1) then PC	<b>←</b>	PC + k + 1	None	1/2
BRVC	k	Branch if Overflow Flag is Cleared	if (V = 0) then PC	<b>←</b>	PC + k + 1	None	1/2
BRIE	k	Branch if Interrupt Enabled	if (I = 1) then PC	<b>←</b>	PC + k + 1	None	1/2
BRID	k	Branch if Interrupt Disabled	if (I = 0) then PC	<b>←</b>	PC + k + 1	None	1/2
		Data T	ransfer Instructions				
MOV	Rd, Rr	Copy Register	Rd	<b>←</b>	Rr	None	1
MOVW	Rd, Rr	Copy Register Pair	Rd+1:Rd	<b>←</b>	Rr+1:Rr	None	1
LDI	Rd, K	Load Immediate	Rd	<b>←</b>	К	None	1
LDS	Rd, k	Load Direct from data space	Rd	<b>←</b>	(k)	None	2 <sup>(1)(2)</sup>
LD	Rd, X	Load Indirect	Rd	<b>←</b>	(X)	None	1 <sup>(1)(2)</sup>
LD	Rd, X+	Load Indirect and Post-Increment	Rd X	← ←	(X) X+1	None	1 <sup>(1)(2)</sup>
LD	Rd, -X	Load Indirect and Pre-Decrement	$X \leftarrow X - 1$ , $Rd \leftarrow (X)$	← ←	X - 1 (X)	None	2 <sup>(1)(2)</sup>
LD	Rd, Y	Load Indirect	$Rd \leftarrow (Y)$	<u>·</u>	(Y)	None	1(1)(2)
LD	Rd, Y+	Load Indirect and Post-Increment	Rd	<u>·</u>	(Y)	None	1 <sup>(1)(2)</sup>
-=	,		Y	<b>←</b>	Y + 1	1.00	



Mnemonics	Operands	Description	Opera	ation		Flags	#Clocks
LD	Rd, -Y	Load Indirect and Pre-Decrement	Y Rd	<b>←</b>	Y - 1 (Y)	None	2 <sup>(1)(2)</sup>
LDD	Rd, Y+q	Load Indirect with Displacement	Rd	<b>←</b>	(Y + q)	None	2 <sup>(1)(2)</sup>
LD	Rd, Z	Load Indirect	Rd	<b>←</b>	(Z)	None	1(1)(2)
LD	Rd, Z+	Load Indirect and Post-Increment	Rd Z	<b>←</b>	(Z), Z+1	None	1 <sup>(1)(2)</sup>
LD	Rd, -Z	Load Indirect and Pre-Decrement	Z Rd	<b>←</b>	Z - 1, (Z)	None	2 <sup>(1)(2)</sup>
LDD	Rd, Z+q	Load Indirect with Displacement	Rd	<b>←</b>	(Z + q)	None	2 <sup>(1)(2)</sup>
STS	k, Rr	Store Direct to Data Space	(k)	<b>←</b>	Rd	None	2 <sup>(1)</sup>
ST	X, Rr	Store Indirect	(X)	<b>←</b>	Rr	None	1 <sup>(1)</sup>
ST	X+, Rr	Store Indirect and Post-Increment	(X) X	<b>←</b>	Rr, X + 1	None	1 <sup>(1)</sup>
ST	-X, Rr	Store Indirect and Pre-Decrement	X (X)	<b>←</b>	X - 1, Rr	None	2 <sup>(1)</sup>
ST	Y, Rr	Store Indirect	(Y)	<b>←</b>	Rr	None	1 <sup>(1)</sup>
ST	Y+, Rr	Store Indirect and Post-Increment	(Y) Y	<b>←</b>	Rr, Y + 1	None	1 <sup>(1)</sup>
ST	-Y, Rr	Store Indirect and Pre-Decrement	Y (Y)	<b>←</b>	Y - 1, Rr	None	2 <sup>(1)</sup>
STD	Y+q, Rr	Store Indirect with Displacement	(Y + q)	←	Rr	None	2 <sup>(1)</sup>
ST	Z, Rr	Store Indirect	(Z)	<b>←</b>	Rr	None	1 <sup>(1)</sup>
ST	Z+, Rr	Store Indirect and Post-Increment	(Z) Z	<b>←</b>	Rr Z + 1	None	1 <sup>(1)</sup>
ST	-Z, Rr	Store Indirect and Pre-Decrement	Z	<b>←</b>	Z - 1	None	2 <sup>(1)</sup>
STD	Z+q,Rr	Store Indirect with Displacement	(Z + q)	<b>←</b>	Rr	None	2 <sup>(1)</sup>
LPM		Load Program Memory	R0	<b>←</b>	(Z)	None	3
LPM	Rd, Z	Load Program Memory	Rd	<b>←</b>	(Z)	None	3
LPM	Rd, Z+	Load Program Memory and Post-Increment	Rd Z	<b>←</b>	(Z), Z + 1	None	3
ELPM		Extended Load Program Memory	R0	←	(RAMPZ:Z)	None	3
ELPM	Rd, Z	Extended Load Program Memory	Rd	←	(RAMPZ:Z)	None	3
ELPM	Rd, Z+	Extended Load Program Memory and Post- Increment	Rd Z	<b>←</b>	(RAMPZ:Z), Z + 1	None	3
SPM		Store Program Memory	(RAMPZ:Z)	←	R1:R0	None	-
SPM	Z+	Store Program Memory and Post-Increment by 2	(RAMPZ:Z) Z	<b>←</b>	R1:R0, Z+2	None	-
IN	Rd, A	In From I/O Location	Rd	<b>←</b>	I/O(A)	None	1
OUT	A, Rr	Out To I/O Location	I/O(A)	<b>←</b>	Rr	None	1
PUSH	Rr	Push Register on Stack	STACK	<b>←</b>	Rr	None	1 <sup>(1)</sup>
POP	Rd	Pop Register from Stack	Rd	<b>←</b>	STACK	None	2 <sup>(1)</sup>
	•	Bit and	Bit-test Instructions				•
LSL	Rd	Logical Shift Left	Rd(n+1) Rd(0) C	<b>↓ ↓</b>	Rd(n), 0, Rd(7)	Z,C,N,V,H	1
LSR	Rd	Logical Shift Right	Rd(n) Rd(7) C	<b>←</b> <b>←</b>	Rd(n+1), 0, Rd(0)	Z,C,N,V	1





Mnemonics	Operands	Description	Opera	tion		Flags	#Clocks
ROL	Rd	Rotate Left Through Carry	Rd(0) Rd(n+1) C	← ← ←	C, Rd(n), Rd(7)	Z,C,N,V,H	1
ROR	Rd	Rotate Right Through Carry	Rd(7) Rd(n) C	← ← ←	C, Rd(n+1), Rd(0)	Z,C,N,V	1
ASR	Rd	Arithmetic Shift Right	Rd(n)	<b>←</b>	Rd(n+1), n=06	Z,C,N,V	1
SWAP	Rd	Swap Nibbles	Rd(30)	$\leftrightarrow$	Rd(74)	None	1
BSET	s	Flag Set	SREG(s)	<b>←</b>	1	SREG(s)	1
BCLR	s	Flag Clear	SREG(s)	<b>←</b>	0	SREG(s)	1
SBI	A, b	Set Bit in I/O Register	I/O(A, b)	<b>←</b>	1	None	1
CBI	A, b	Clear Bit in I/O Register	I/O(A, b)	<b>←</b>	0	None	1
BST	Rr, b	Bit Store from Register to T	Т	<b>←</b>	Rr(b)	Т	1
BLD	Rd, b	Bit load from T to Register	Rd(b)	<b>←</b>	Т	None	1
SEC		Set Carry	С	<b>←</b>	1	С	1
CLC		Clear Carry	С	<b>←</b>	0	С	1
SEN		Set Negative Flag	N	<b>←</b>	1	N	1
CLN		Clear Negative Flag	N	<b>←</b>	0	N	1
SEZ		Set Zero Flag	Z	<b>←</b>	1	Z	1
CLZ		Clear Zero Flag	Z	<b>←</b>	0	Z	1
SEI		Global Interrupt Enable	I	<b>←</b>	1	ı	1
CLI		Global Interrupt Disable	1	<b>←</b>	0	I	1
SES		Set Signed Test Flag	S	<b>←</b>	1	S	1
CLS		Clear Signed Test Flag	S	<b>←</b>	0	S	1
SEV		Set Two's Complement Overflow	V	<b>←</b>	1	V	1
CLV		Clear Two's Complement Overflow	V	<b>←</b>	0	V	1
SET		Set T in SREG	Т	<b>←</b>	1	Т	1
CLT		Clear T in SREG	Т	<b>←</b>	0	Т	1
SEH		Set Half Carry Flag in SREG	Н	<b>←</b>	1	Н	1
CLH		Clear Half Carry Flag in SREG	Н	<b>←</b>	0	Н	1
		MCU (	Control Instructions				
BREAK		Break	(See specific des	scr. for	BREAK)	None	1
NOP		No Operation				None	1
SLEEP		Sleep	(see specific de	scr. fo	r Sleep)	None	1
WDR		Watchdog Reset	(see specific de	scr. fo	r WDR)	None	1

- Notes: 1. Cycle times for Data memory accesses assume internal memory accesses, and are not valid for accesses via the external RAM interface.
  - 2. One extra cycle must be added when accessing Internal SRAM.

# 33. Packaging information

# 33.1 64A





# COMMON DIMENSIONS

(Unit of measure = mm)

SYMBOL	MIN	NOM	MAX	NOTE
Α	_	_	1.20	
A1	0.05	-	0.15	
A2	0.95	1.00	1.05	
D	15.75	16.00	16.25	
D1	13.90	14.00	14.10	Note 2
Е	15.75	16.00	16.25	
E1	13.90	14.00	14.10	Note 2
В	0.30	-	0.45	
С	0.09	-	0.20	
L	0.45	_	0.75	
е		0.80 TYP		

#### 2010-10-20

#### Notes:

- 1. This package conforms to JEDEC reference MS-026, Variation AEB.
- Dimensions D1 and E1 do not include mold protrusion. Allowable protrusion is 0.25mm per side. Dimensions D1 and E1 are maximum plastic body size dimensions including mold mismatch.
- 3. Lead coplanarity is 0.10mm maximum.

AMEL

2325 Orchard Parkway San Jose, CA 95131


#### TITLE

 $\textbf{64A,} \ \textbf{64-lead}, \ \textbf{14} \ \textbf{x} \ \textbf{14mm} \ \textbf{Body} \ \textbf{Size}, \ \textbf{1.0mm} \ \textbf{Body} \ \textbf{Thickness}, \\ \textbf{0.8mm} \ \textbf{Lead} \ \textbf{Pitch}, \ \textbf{Thin} \ \textbf{Profile} \ \textbf{Plastic} \ \textbf{Quad} \ \textbf{Flat} \ \textbf{Package} \ (\textbf{TQFP})$ 

DRAWING NO.	REV.
64A	С



### 33.2 64M2



# 34. Electrical Characteristics

#### **Absolute Maximum Ratings\*** 34.1

Operating Temperature55°C to +125°C
Storage Temperature65°C to +150°C
Voltage on any Pin with respect to Ground0.5V to $V_{CC}$ +0.5V
Maximum Operating Voltage
DC Current per I/O Pin20.0 mA
DC Current V <sub>CC</sub> and GND Pins200.0 mA

\*NOTICE:

Stresses beyond those listed under "Absolute Maximum Ratings" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at these or other conditions beyond those indicated in the operational sections of this specification is not implied. Exposure to absolute maximum rating conditions for extended periods may affect device reliability.

#### 34.2 **DC Characteristics**

**Current Consumption Table 34-1.** 

Symbol	Parameter	Condit	Condition			Тур	Max	Units	
			20 kH= Fv4 Olk	V <sub>CC</sub> = 1.8V		25			
			32 kHz, Ext. Clk	$V_{CC} = 3.0V$		71			
			1 MHz, Ext. Clk	V <sub>CC</sub> = 1.8V		317			
		Active		V <sub>CC</sub> = 3.0V		697		μA	
			OMILE For Oile	V <sub>CC</sub> = 1.8V		613	800		
			2 MHz, Ext. Clk	V <sub>CC</sub> = 3.0V		1340	1800		
	Davier Commby Comment(1)		32 MHz, Ext. Clk	V <sub>CC</sub> = 3.0V		15.7	18	mA	
	Power Supply Current <sup>(1)</sup>		20 Id I= For Olle	V <sub>CC</sub> = 1.8V		3.6			
			32 kHz, Ext. Clk	V <sub>CC</sub> = 3.0V		6.9			
				4 Mills Fut Cile	V <sub>CC</sub> = 1.8V		112		
		Idle	1 MHz, Ext. Clk	$V_{CC} = 3.0V$		215		- μA - -	
I <sub>cc</sub>			2 MHz, Ext. Clk	V <sub>CC</sub> = 1.8V		224	350		
				$V_{CC} = 3.0V$		430	650		
			32 MHz, Ext. Clk	$V_{CC} = 3.0V$		6.9	8	mA	
		All Fund	All Functions Disabled			0.1	3		
		All Fund	ctions Disabled, T = 85°C	$V_{CC} = 3.0V$		1.75	5		
	Power-down mode	LILD W	IDT Compled DOD	V <sub>CC</sub> = 1.8V		1			
		ULP, VV	DT, Sampled BOD	$V_{CC} = 3.0V$		1	6		
		ULP, W	DT, Sampled BOD, T=85°C	$V_{CC} = 3.0V$		2.7	10	μA	
		RTC 1	kHz from Low Power 32 kHz	V <sub>CC</sub> = 1.8V		0.55			
	Power-save mode	TOSC		$V_{CC} = 3.0V$		0.65			
		RTC fro	om Low Power 32 kHz TOSC	$V_{CC} = 3.0V$		1.16			
	Reset Current Consumption	without	Reset pull-up resistor current	V <sub>CC</sub> = 3.0V		1300			

Table 34-1. **Current Consumption** 

Symbol	Parameter	Condition	Min	Тур	Max	Units	
Module o	urrent consumption <sup>(2)</sup>						
	RC32M			460			
	RC32M w/DFLL	Internal 32.768 kHz oscillator as DFLL source		594			
	RC2M			101			
	RC2M w/DFLL	Internal 32.768 kHz oscillator as DFLL source		134			
	RC32K			27			
	PLL	Multiplication factor = 10x		202			
	Watchdog normal mode			1		μA	
	BOD Continuous mode			128			
	BOD Sampled mode			1			
	Internal 1.00 V ref			80			
	Temperature reference			74			
	RTC with int. 32 kHz RC as source	No prescaling		27			
	RTC with ULP as source	No prescaling		1			
I <sub>CC</sub>	ADC 250 kS/s - Int. 1V Ref			2.9			
	DAC Normal Mode	1000 kS/s, Single channel, Int. 1V Ref		1.8			
	DAC Low-Power Mode	1000 KS/s, Single channel, Int. 1V Ref		0.95		mA	
	DAC S/H Normal Mode	Int.1.1V Ref, Refresh 16CLK		2.9		·\	
	DAC Low-Power Mode S/H	Int.1.1V Ref, Refresh 16CLK		1.1			
	AC High-speed			195			
	AC Low-power			103			
	USART	Rx and Tx enabled, 9600 BAUD		5.4		^	
	DMA			128		μA	
	Timer/Counter	Prescaler DIV1		20			
	AES			223			
	Flash/EEPROM	Vcc = 2V		25		^	
	Programming	Vcc = 3V		33		mA	

2. All parameters measured as the difference in current consumption between module enabled and disabled. All data at  $V_{CC}$  = 3.0V,  $Clk_{SYS}$  = 1 MHz External clock with no prescaling, T = 25°C.


#### **Operating Voltage and Frequency** 34.3

Table 34-2. Operating voltage and frequency

Symbol	Parameter	Condition	Min	Тур	Max	Units
		V <sub>CC</sub> = 1.6V	0		12	
0.11	CDI I ala ali fira muana u	V <sub>CC</sub> = 1.8V	0		12	N 41 1-
Clk <sub>CPU</sub>	_	V <sub>CC</sub> = 2.7V	0		32	MHz
		V <sub>CC</sub> = 3.6V	0		32	

The maximum CPU clock frequency of the XMEGA A3B devices is depending on  $V_{\text{CC}}$ . As shown in Figure 34-1 on page 66 the Frequency vs.  $V_{CC}$  curve is linear between 1.8V <  $V_{CC}$  < 2.7V.

Figure 34-1. Maximum Frequency vs. Vcc



# 34.4 Flash and EEPROM Memory Characteristics

**Table 34-3.** Endurance and Data Retention

Symbol	Parameter	Condition	Condition		Тур	Max	Units	
		Write/Erase cycles	Muita/Europa avalop	25°C	10K			Cuala
			write/Erase cycles	85°C	10K			Cycle
	Flash	Data retention	25°C	100			Vaar	
		Data retention	55°C	25			Year	
		\\\\-it=\ \Gamma=========	25°C	80K			0	
	EEPROM	Write/Erase cycles	85°C	30K			Cycle	
		Determination	25°C	100			V	
		Data retention	55°C	25			Year	

 Table 34-4.
 Programming time

Symbol	Parameter	Condition	Min	Typ <sup>(1)</sup>	Max	Units
	Chip Erase	Flash, EEPROM <sup>(2)</sup> and SRAM Erase		40		
	Flash	Page Erase		6		
		Page Write		6		
		Page Write Automatic Page Erase and Write		12		ms
		Page Erase		6		
		Page Write		6		
		Page Write Automatic Page Erase and Write		12		

Notes: 1. Programming is timed from the internal 2 MHz oscillator.

2. EEPROM is not erased if the EESAVE fuse is programmed.

# 34.5 ADC Characteristics

Table 34-5. **ADC Characteristics** 

Symbol	Parameter	Condition	Min	Тур	Max	Units
RES	Resolution	Programmable: 8/12	8	12	12	Bits
INL	Integral Non-Linearity	500 ksps		±2		LCD
DNL	Differential Non-Linearity	500 ksps		< ±1		LSB
	Gain Error			< ±10		>/
	Offset Error			< ±2		mV
ADC <sub>clk</sub>	ADC Clock frequency	Max is 1/4 of Peripheral Clock			2000	kHz
	Conversion rate				2000	ksps
	Conversion time (propagation delay)	(RES+2)/2+GAIN RES = 8 or 12, GAIN = 0 or 1	5	7	8	ADC <sub>clk</sub> cycles
	Sampling Time	1/2 ADC <sub>clk</sub> cycle	0.25			uS
	Conversion range		0		VREF	
AVCC	Analog Supply Voltage		V <sub>cc</sub> -0.3		V <sub>cc</sub> +0.3	V
VREF	Reference voltage		1.0		V <sub>cc</sub> -0.6V	
	Input bandwidth					kHz
INT1V	Internal 1.00V reference			1.00		
INTVCC	Internal V <sub>CC</sub> /1.6			V <sub>CC</sub> /1.6		V
SCALEDVCC	Scaled internal V <sub>CC</sub> /10 input			V <sub>CC</sub> /10		
R <sub>AREF</sub>	Reference input resistance			> 10		ΜΩ
	Start-up time			12	24	ADC <sub>clk</sub> cycles
	Internal input sampling speed	Temp. sensor, V <sub>CC</sub> /10, Bandgap			100	ksps

 Table 34-6.
 ADC Gain Stage Characteristics

Symbol	Parameter	Condition		Min	Тур	Max	Units
	Gain error	1 to 64 gain			< ±1		%
	Offset error				< ±1		
\ /****	Noise level at input	64x gain	VREF = Int. 1V		0.12		mV
Vrms			VREF = Ext. 2V		0.06		
	Clock rate	Same as ADC				1000	kHz

#### 34.6 **DAC Characteristics**

Table 34-7. DAC Characteristics

Symbol	Parameter	Co	ndition	Min	Тур	Max	Units
INL	Integral Non-Linearity	V <sub>CC</sub> = 1.6-3.6V	VREF = Ext. ref		5		
DNII	Differential Non-Linearity	1.0.0.01	VREF = Ext. ref		<±1		LSB
DNL		$V_{CC} = 1.6-3.6V$	VREF= AV <sub>CC</sub>				
F <sub>clk</sub>	Conversion rate		,			1000	ksps
AREF	External reference voltage			1.1		AV <sub>CC</sub> -0.6	V
	Reference input impedance				>10		MΩ
	Max output voltage	$R_{load}$ =100k $\Omega$			AV <sub>CC</sub> *0.98		
	Min output voltage	$R_{load}$ =100k $\Omega$			0.015		V
	Offset factory calibration accuracy	Continues mode, \	Continues mode, V <sub>CC</sub> =3.0V,		±0.5		1.00
	Gain factory calibration accuracy		F = Int 1.00V, T=85°C		±2.5		LSB

# 34.7 Analog Comparator Characteristics

Table 34-8. **Analog Comparator Characteristics** 

Symbol	Parameter	Condition		Min	Тур	Max	Units
$V_{\rm off}$	Input Offset Voltage	V <sub>CC</sub> = 1.6 - 3.6V			<±10		mV
I <sub>lk</sub>	Input Leakage Current	V <sub>CC</sub> = 1.6 - 3.6V			< 1000		pA
V <sub>hys1</sub>	Hysteresis, No	V <sub>CC</sub> = 1.6 - 3.6V			0		mV
V <sub>hys2</sub>	Hysteresis, Small	V <sub>CC</sub> = 1.6 - 3.6V	mode = HS		20		.,
V <sub>hys3</sub>	Hysteresis, Large	V <sub>CC</sub> = 1.6 - 3.6V	mode = HS		40		mV
		V <sub>CC</sub> = 3.0V, T= 85°C	mode = HS			100	
t <sub>delay</sub>	Propagation delay	V <sub>CC</sub> = 1.6 - 3.6V	mode = HS		110		ns
		V <sub>CC</sub> = 1.6 - 3.6V	mode = LP		175		

#### **Bandgap Characteristics** 34.8

Bandgap Voltage Characteristics Table 34-9.

Symbol	Parameter	Condition	Min	Тур	Max	Units
	Dandran	As reference for ADC or DAC	1 CI	1 Clk_PER + 2.5μs		
	Bandgap	As input to AC or ADC		1.5		μs
	Bandgap voltage			1.1		
	ADC/DAC ref	T= 85°C, After calibration	0.99	1	1.01	V
				1		
	Variation over voltage and temperature	$V_{CC} = 1.6 - 3.6V, T = -40^{\circ}C \text{ to } 85^{\circ}C$		±5		%

# 34.9 Brownout Detection Characteristics

**Table 34-10.** Brownout Detection Characteristics<sup>(1)</sup>

Symbol	Parameter	Condition	Min	Тур	Max	Units
	BOD level 0 falling Vcc			1.62		
	BOD level 1 falling Vcc			1.9		
	BOD level 2 falling Vcc			2.17		
	BOD level 3 falling Vcc			2.43		\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \
	BOD level 4 falling Vcc			2.68		V
	BOD level 5 falling Vcc			2.96		
	BOD level 6 falling Vcc			3.22		
	BOD level 7 falling Vcc			3.49		
	Hysteresis	BOD level 0-5		1		%

Note: 1. BOD is calibrated on BOD level 0 at 85°C.

# 34.10 PAD Characteristics

Table 34-11. PAD Characteristics

Symbol	Parameter	Condition	Min	Тур	Max	Units
	logot High Voltage	V <sub>CC</sub> = 2.4 - 3.6V	0.7*V <sub>CC</sub>		V <sub>CC</sub> +0.5	
$V_{IH}$	Input High Voltage	V <sub>CC</sub> = 1.6 - 2.4V	0.8*V <sub>CC</sub>		V <sub>CC</sub> +0.5	
\ /	Input Low Voltage	V <sub>CC</sub> = 2.4 - 3.6V	-0.5		0.3*V <sub>CC</sub>	
$V_{IL}$		V <sub>CC</sub> = 1.6 - 2.4V	-0.5		0.2*V <sub>CC</sub>	
	Output Low Voltage GPIO	$I_{OH} = 15 \text{ mA}, V_{CC} = 3.3 \text{V}$		0.4	0.76	.,
$V_{OL}$		$I_{OH} = 10 \text{ mA}, V_{CC} = 3.0 \text{V}$		0.3	0.64	V
		$I_{OH} = 5 \text{ mA}, V_{CC} = 1.8 \text{V}$		0.2	0.46	
	Output High Voltage GPIO	$I_{OH} = -8 \text{ mA}, V_{CC} = 3.3 \text{V}$	2.6	2.9		
$V_{OH}$		$I_{OH} = -6 \text{ mA}, V_{CC} = 3.0 \text{V}$	2.1	2.7		
		$I_{OH} = -2 \text{ mA}, V_{CC} = 1.8 \text{V}$	1.4	1.6		
I <sub>IL</sub>	Input Leakage Current I/O pin			<0.001	1	
I <sub>IH</sub>	Input Leakage Current I/O pin			<0.001	1	μA
$R_P$	I/O pin Pull/Buss keeper Resistor			20		Lo
R <sub>RST</sub>	Reset pin Pull-up Resistor			20		kΩ
	Input hysteresis			0.5		V

# 34.11 POR Characteristics

Table 34-12. Power-on Reset Characteristics

Symbol	Parameter	Condition	Min	Тур	Max	Units
V <sub>POT-</sub>	POR threshold voltage falling Vcc			1		M
V <sub>POT+</sub>	POR threshold voltage rising Vcc			1.45		V

# 34.12 Reset Characteristics

# Table 34-13. Reset Characteristics

Symbol	Parameter	Condition	Min	Тур	Max	Units
	Minimum reset pulse width			90		ns
	Reset threshold voltage	V <sub>CC</sub> = 2.7 - 3.6V		0.45*V <sub>CC</sub>		\/
		V <sub>CC</sub> = 1.6 - 2.7V		0.42*V <sub>CC</sub>		V

# 34.13 Oscillator Characteristics

### Table 34-14. Internal 32.768 kHz Oscillator Characteristics

Symbol	Parameter	Condition	Min	Тур	Max	Units
	Accuracy	$T = 85$ °C, $V_{CC} = 3V$ , After production calibration	-0.5		0.5	%

# Table 34-15. Internal 2 MHz Oscillator Characteristics

Symbol	Parameter	Condition	Min	Тур	Max	Units
	Accuracy	$T = 85$ °C, $V_{CC} = 3V$ , After production calibration	-1.5		1.5	%
	DFLL Calibration step size	T = 25°C, V <sub>CC</sub> = 3V		0.15		

#### Table 34-16. Internal 32 MHz Oscillator Characteristics

Symbol	Parameter	Condition	Min	Тур	Max	Units
	Accuracy	$T = 85$ °C, $V_{CC} = 3V$ , After production calibration	-1.5		1.5	%
	DFLL Calibration stepsize	T = 25°C, V <sub>CC</sub> = 3V		0.2		

# Table 34-17. Internal 32 kHz, ULP Oscillator Characteristics

Symbol	Parameter	Condition	Min	Тур	Max	Units
	Output frequency 32 kHz ULP OSC	$T = 85^{\circ}C, V_{CC} = 3.0V$		26		kHz

Table 34-18. Maximum load capacitance (CL) and ESR recommendation for 32.768 kHz Crystal

Crystal CL [pF]	Max ESR [kΩ]		
6.5	60		
9	35		

Table 34-19. Device wake-up time from sleep

Symbol	Parameter	Condition (1)	Min	Typ <sup>(2)</sup>	Max	Units
	Idle Sleep, Standby and Extended Standby sleep mode	Int. 32.768 kHz RC		130		
		Int. 2 MHz RC		2		
		Ext. 2 MHz Clock		2		
		Int. 32 MHz RC		0.17		μS
	Power-save and Power-down Sleep mode	Int. 32.768 kHz RC		320		
		Int. 2 MHz RC		10.3		
		Ext. 2 MHz Clock		4.5		
		Int. 32 MHz RC		5.8		

Notes: 1. Non-prescaled System Clock source.

<sup>2.</sup> Time from pin change on external interrupt pin to first available clock cycle. Additional interrupt response time is minimum 5 system clock source cycles.

# 34.14 VBAT and Battery Backup Characteristics


Table 34-20. VBAT and Battery Backup Characteristics

Symbol	Parameter	Condition	Min	Тур	Max	Units
	Vbat supply voltage range		Vbbbod		3.6	V
	Vbat power-on slope rate	Monotonic rising	0.2			V/ms
	Vcc Power-loss slope range	Monotonic falling			0.1	V/ms
	main BOD threshold voltage		1.8			V
	BBBOD required voltage change			1.2		V
	BBBOD threshold voltage			1.7	2.1	V
	BBBOD detection speed			1	2	S
	Battery Backup System current	RTC enabled from 1 Hz TOSC with XOSC Failure Monitor enabled		530		nA
	consumption	RTC enabled from 1 Hz Hi ESR mode and XOSC Failure Monitor enabled		680		nA
	VBAT pin leackage	Powering Battery Backup module from Vcc			50	nA
	Delay from setting XOSCFDEN to setting XOSCEN		200			μS
	Missing crystal oscillator cycles before XOSCFAIL is set			32		cycles


# 35. Typical Characteristics

# 35.1 Active Supply Current


**Figure 35-1.** Active Supply Current vs. Frequency  $f_{SYS} = 0$  - 1.0 MHz External clock, T = 25°C




**Figure 35-2.** Active Supply Current vs. Frequency  $f_{SYS} = 1 - 32$  MHz External clock, T = 25°C



**Figure 35-3.** Active Supply Current vs. Vcc  $f_{SYS} = 1.0 \text{ MHz External Clock}$ 



**Figure 35-4.** Active Supply Current vs. VCC  $f_{SYS} = 32.768 \text{ kHz internal RC}$ 



Not recommended for new designs -

Use ATxmega256A3BU

**Figure 35-5.** Active Supply Current vs. Vcc  $f_{SYS} = 2.0 \text{ MHz internal RC}$ 





Figure 35-6. Active Supply Current vs. Vcc  $f_{SYS} = 32 \text{ MHz internal RC prescaled to 8 MHz}$ 



25 -40 °C 25 °C 85 °C 20 15 Icc [mA] 10 5 0 2.7 2.8 2.9 3 3.1 3.2 3.3 3.4 3.5 3.6  $V_{CC}[V]$ 

Figure 35-7. Active Supply Current vs. Vcc

# $f_{SYS} = 32 MHz internal RC$

# 35.2 Idle Supply Current

**Figure 35-8.** Idle Supply Current vs. Frequency  $f_{SYS} = 0 - 1.0 \text{ MHz}, T = 25^{\circ}\text{C}$ 




Figure 35-9. Idle Supply Current vs. Frequency

 $f_{SYS} = 1 - 32 \text{ MHz}, T = 25^{\circ}\text{C}$ 




Figure 35-10. Idle Supply Current vs. Vcc

 $f_{SYS} = 1.0 MHz$  External Clock




Figure 35-11. Idle Supply Current vs. Vcc

 $f_{SYS} = 32.768 \text{ kHz internal RC}$ 




Figure 35-12. Idle Supply Current vs. Vcc

 $f_{\rm SYS} = 2.0$  MHz internal RC




Figure 35-13. Idle Supply Current vs. Vcc

 $f_{\rm SYS} = 32$  MHz internal RC prescaled to 8 MHz






Figure 35-14. Idle Supply Current vs. Vcc

 $f_{SYS} = 32 \text{ MHz internal RC}$ 




# 35.3 Power-down Supply Current






**Figure 35-16.** Power-down Supply Current vs. Temperature With WDT and sampled BOD enabled.




# 35.4 Power-save Supply Current

**Figure 35-17.** Power-save Supply Current vs. Temperature With WDT, sampled BOD and RTC from ULP enabled



# 35.5 Pin Pull-up

Figure 35-18. Reset Pull-up Resistor Current vs. Reset Pin Voltage







Figure 35-19. Reset Pull-up Resistor Current vs. Reset Pin Voltage






Not recommended for new designs -


Use ATxmega256A3BU

# 35.6 Pin Output Voltage vs. Sink/Source Current

Figure 35-21. I/O Pin Output Voltage vs. Source Current



**Figure 35-22.** I/O Pin Output Voltage vs. Source Current Vcc = 3.0V








Figure 35-23. I/O Pin Output Voltage vs. Source Current





0.7 0.6 0.5 0.4 0.3 0.2 0.1 0.7 85 °C 25 °C -40 °C

10

 $I_{PIN}$  [mA]

12

14

16

18

20

**Figure 35-25.** I/O Pin Output Voltage vs. Sink Current Vcc = 3.0V

Figure 35-26. I/O Pin Output Voltage vs. Sink Current Vcc = 3.3V


4

6

8

0

2



Not recommended for new designs -

Use ATxmega256A3BU

# 35.7 Pin Thresholds and Hysteresis

Figure 35-27. I/O Pin Input Threshold Voltage vs.  $V_{CC}$   $V_{IH}$  - I/O Pin Read as "1"





Figure 35-28. I/O Pin Input Threshold Voltage vs.  $V_{\rm CC}$ 







Figure 35-29. I/O Pin Input Hysteresis vs.  $V_{\rm CC}$ 






1.8 -40 °C 25 °C 85 °C 1.6 1.4 1.2 Vтняеѕно∟ [V] 0.8 0.6 0.4 0.2 0 1.6 2 2.2 2.4 2.6 2.8 3 3.2 3.4 3.6 1.8  $V_{CC}[V]$ 

Figure 35-31. Reset Input Threshold Voltage vs.  $V_{CC}$   $V_{IL}$  - I/O Pin Read as "0"

# 35.8 Bod Thresholds

**Figure 35-32.** BOD Thresholds vs. Temperature BOD Level = 1.6V








Figure 35-33. BOD Thresholds vs. Temperature

# 35.9 Oscillators and Wake-up Time

## 35.9.1 Internal 32.768 kHz Oscillator





# 35.9.2 Internal 2 MHz Oscillator

**Figure 35-35.** Internal 2 MHz Oscillator CALA Calibration Step Size T = -40 to 85 °C,  $V_{\rm CC} = 3V$ 






Figure 35-36. Internal 2 MHz Oscillator CALB Calibration Step Size




# 35.9.3 Internal 32 MHZ Oscillator

**Figure 35-37.** Internal 32 MHz Oscillator CALA Calibration Step Size T = -40 to 85°C,  $V_{CC} = 3V$ 



**Figure 35-38.** Internal 32 MHz Oscillator CALB Calibration Step Size T = -40 to 85°C,  $V_{CC} = 3V$ 



# 35.10 Module current consumption

Figure 35-39. AC current consumption vs. Vcc Low-power Mode






Figure 35-40. Power-up current consumption vs. Vcc




# 35.11 Reset Pulsewidth





# 35.12 PDI Speed

Figure 35-42. PDI Speed vs. Vcc



# 36. Errata

# 36.1 ATxmega256A3B

#### 36.1.1 rev. C

- . Bandgap voltage input for the ACs can not be changed when used for both ACs simultaneously
- VCC voltage scaler for AC is non-linear
- ADC has increased INL error for some operating conditions
- ADC gain stage non-functional
- ADC Event on compare match non-functional
- Bandgap measurement with the ADC is non-functional when VCC is below 2.7V
- Configuration of PGM and CWCM not as described in XMEGA A Manual
- PWM is not restarted properly after a fault in cycle-by-cycle mode
- · BOD will be enabled at any reset
- DAC is nonlinear and inaccurate when reference is above 2.4V or VCC 0.6V
- DAC has increased INL or noise for some operating conditions
- · DAC refresh may be blocked in S/H mode
- Conversion lost on DAC channel B in event triggered mode
- EEPROM page buffer always written when NVM DATA0 is written
- Pending full asynchronous pin change interrupts will not wake the device
- Pin configuration does not affect Analog Comparator Output
- NMI Flag for Crystal Oscillator Failure automatically cleared
- · Crystal start-up time required after power-save even if crystal is source for RTC
- TWI Transmit collision flag not cleared on repeated start
- . Clearing TWI Stop Interrupt Flag may lock the bus
- TWI START condition at bus timeout will cause transaction to be dropped
- TWI Data Interrupt Flag (DIF) erroneously read as set
- WDR instruction inside closed window will not issue reset
- Pending asynchronous RTC32-interrupts will not wake up device
- XOSCDFD can not be cleared by writing one to bit location
- Maximum operating frequency below 1.76V is 8 MHz

# Bandgap voltage input for the ACs cannot be changed when used for both ACs simultaneously

If the Bandgap voltage is selected as input for one Analog Comparator (AC) and then selected/deselected as input for another AC, the first comparator will be affected for up to 1 µs and could potentially give a wrong comparison result.


#### Problem fix/Workaround

If the Bandgap is required for both ACs simultaneously, configure the input selection for both ACs before enabling any of them.

#### 2. VCC voltage scaler for AC is non-linear

The 6-bit VCC voltage scaler in the Analog Comparators is non-linear.





**Figure 36-1.** Analog Comparator Voltage Scaler vs. Scalefac  $T = 25^{\circ}C$ 

#### Problem fix/Workaround

Use external voltage input for the analog comparator if accurate voltage levels are needed

## 3. ADC has increased INL error for some operating conditions

Some ADC configurations or operating condition will result in increased INL error.

In signed mode INL is increased to:

- 6 LSB for sample rates above 1 Msps, and up to 8 LSB for 2 Msps sample rate.
- 6 LSB for reference voltage below 1.1V when VCC is above 3.0V.
- 20 LSB for ambient temperature below 0 degree C and reference voltage below 1.3V.
   In unsigned mode, the INL is increased up to a factor of 3 for the conditions above.

#### Problem fix/Workaround

None, avoid using the ADC in the above configurations in order to prevent increased INL error.

#### 4. ADC gain stage non-functional

The ADC gain stage is non-functional.

#### Problem fix/Workaround

None.

## 5. ADC Event on compare match non-functional

ADC signalling event will be given at every conversion complete even if Interrupt mode (INT-MODE) is set to BELOW or ABOVE.

#### Problem fix/Workaround

Enable and use interrupt on compare match when using the compare function.

# 6. Bandgap measurement with the ADC is non-functional when VCC is below 2.7V The ADC can not be used to do bandgap measurements when VCC is below 2.7V.



#### Problem fix/Workaround

None.

## 7. Configuration of PGM and CWCM not as described in XMEGA A Manual

Enabling Common Waveform Channel Mode will enable Pattern generation mode (PGM), but not Common Waveform Channel Mode.

Enabling Pattern Generation Mode (PGM) and not Common Waveform Channel Mode (CWCM) will enable both Pattern Generation Mode and Common Waveform Channel Mode.

#### Problem fix/Workaround

**Table 36-1.** Configure PWM and CWCM according to this table:

PGM	CWCM	Description
0	0	PGM and CWCM disabled
0	1	PGM enabled
1	0	PGM and CWCM enabled
1	1	PGM enabled

## 8. PWM is not restarted properly after a fault in cycle-by-cycle mode

When the AWeX fault restore mode is set to cycle-by-cycle, the waveform output will not return to normal operation at first update after fault condition is no longer present.

#### Problem fix/Workaround

Do a write to any AWeX I/O register to re-enable the output.

#### 9. BOD will be enabled after any reset

If any reset source goes active, the BOD will be enabled and keep the device in reset if the VCC voltage is below the programmed BOD level. During Power-On Reset, reset will not be released until VCC is above the programmed BOD level even if the BOD is disabled.

#### Problem fix/Workaround

Do not set the BOD level higher than VCC even if the BOD is not used.

#### 10. DAC is nonlinear and inaccurate when reference is above 2.4V or VCC - 0.6V

Using the DAC with a reference voltage above 2.4V or VCC - 0.6V will give inaccurate output when converting codes that give below 0.75V output:

- ±10 LSB for continuous mode
- ±200 LSB for Sample and Hold mode

#### Problem fix/Workaround

None.

#### 11. DAC has increased INL or noise for some operating conditions

Some DAC configurations or operating condition will result in increased output error.

- Continous mode: ±5 LSB
- Sample and hold mode: ±15 LSB
- Sample and hold mode for reference above 2.0v: up to ±100 LSB

#### Problem fix/Workaround

None.



#### 12. DAC refresh may be blocked in S/H mode

If the DAC is running in Sample and Hold (S/H) mode and conversion for one channel is done at maximum rate (i.e. the DAC is always busy doing conversion for this channel), this will block refresh signals to the second channel.

#### Problem fix/Workaround

When using the DAC in S/H mode, ensure that none of the channels is running at maximum conversion rate, or ensure that the conversion rate of both channels is high enough to not require refresh.

## 13. Conversion lost on DAC channel B in event triggered mode

If during dual channel operation channel 1 is set in auto trigged conversion mode, channel 1 conversions are occasionally lost. This means that not all data-values written to the Channel 1 data register are converted.

#### Problem fix/Workaround

Keep the DAC conversion interval in the range 000-001 (1 and 3 CLK), and limit the Peripheral clock frequency so the conversion internal never is shorter than 1.5 µs.

#### 14. EEPROM page buffer always written when NVM DATA0 is written

If the EEPROM is memory mapped, writing to NVM DATA0 will corrupt data in the EEPROM page buffer.

#### Problem fix/Workaround

Before writing to NVM DATA0, for example when doing software CRC or flash page buffer write, check if EEPROM page buffer active loading flag (EELOAD) is set. Do not write NVM DATA0 when EELOAD is set.

#### 15. Pending full asynchronous pin change interrupts will not wake the device

Any full asynchronous pin-change Interrupt from pin 2, on any port, that is pending when the sleep instruction is executed, will be ignored until the device is woken from another source or the source triggers again. This applies when entering all sleep modes where the System Clock is stopped.

#### Problem fix/Workaround

None.

# 16. Pin configuration does not affect Analog Comparator output

The Output/Pull and inverted pin configuration does not affect the Analog Comparator output.

#### Problem fix/Workaround

None for Output/Pull configuration.

For inverted I/O, configure the Analog Comparator to give an inverted result (i.e. connect positive input to the negative AC input and vice versa), or use and external inverter to change polarity of Analog Comparator output.

#### 17. NMI Flag for Crystal Oscillator Failure automatically cleared

NMI flag for Crystal Oscillator Failure (XOSCFDIF) will be automatically cleared when executing the NMI interrupt handler.



#### Problem fix/Workaround

This device revision has only one NMI interrupt source, so checking the interrupt source in software is not required.

## 18. Crystal start-up time required after power-save even if crystal is source for RTC

Even if 32.768 kHz crystal is used for RTC during sleep, the clock from the crystal will not be ready for the system before the specified start-up time. See "XOSCSEL[3:0]: Crystal Oscillator Selection" in XMEGA A Manual. If BOD is used in active mode, the BOD will be on during this period (0.5s).

#### Problem fix/Workaround

If faster start-up is required, go to sleep with internal oscillator as system clock.

## 19. TWI Transmit collision flag not cleared on repeated start

The TWI transmit collision flag should be automatically cleared on start and repeated start. but is only cleared on start.

#### Problem fix/Workaround

Clear the flag in software after address interrupt.

## 20. Clearing TWI Stop Interrupt Flag may lock the bus

If software clears the STOP Interrupt Flag (APIF) on the same Peripheral Clock cycle as the hardware sets this flag due to a new address received, CLKHOLD is not cleared and the SCL line is not released. This will lock the bus.

#### Problem fix/Workaround

Check if the bus state is IDLE. If this is the case, it is safe to clear APIF. If the bus state is not IDLE, wait for the SCL pin to be low before clearing APIF.

#### Code:

```
/* Only clear the interrupt flag if within a "safe zone". */
while ( /* Bus not IDLE: */
       ((COMMS TWI.MASTER.STATUS & TWI MASTER BUSSTATE gm) !=
         TWI MASTER BUSSTATE IDLE gc)) &&
         /* SCL not held by slave: */
         !(COMMS TWI.SLAVE.STATUS & TWI SLAVE CLKHOLD bm)
      )
{
    /* Ensure that the SCL line is low */
    if (!(COMMS PORT.IN & PIN1 bm))
        if ( !(COMMS_PORT.IN & PIN1_bm) )
            break;
}
/* Check for an pending address match interrupt */
if ( !(COMMS TWI.SLAVE.STATUS & TWI SLAVE CLKHOLD bm) )
{
    /* Safely clear interrupt flag */
    COMMS TWI.SLAVE.STATUS |= (uint8 t) TWI SLAVE APIF bm;
}
```

#### 21. TWI START condition at bus timeout will cause transaction to be dropped

If Bus Timeout is enabled and a timeout occurs on the same Peripheral Clock cycle as a START is detected, the transaction will be dropped.

#### Problem fix/Workaround

None.

#### 22. TWI Data Interrupt Flag (DIF) erroneously read as set

When issuing the TWI slave response command CMD=0b11, it takes 1 Peripheral Clock cycle to clear the data interrupt flag (DIF). A read of DIF directly after issuing the command will show the DIF still set.

#### Problem fix/Workaround

Add one NOP instruction before checking DIF.

#### 23. WDR instruction inside closed window will not issue reset

When a WDR instruction is execute within one ULP clock cycle after updating the window control register, the counter can be cleared without giving a system reset.

#### Problem fix/Workaround

Wait at least one ULP clock cycle before executing a WDR instruction.

## 24. Pending asynchronous RTC32-interrupts will not wake up device

Asynchronous Interrupts from the 32-bit Real-Time-Counter that is pending when the sleep instruction is executed, will be ignored until the device is woken from another source or the source triggers again.

#### Problem fix/Workaround

None.

#### 25. XOSCDFD can not be cleared by writing one to bit location

The Crystal Oscillator Failure Detection Flag (XOSCFDF) can not be cleared by writing one to its bit location. The bit can only be cleared by issuing a reset to the VBAT domain.

#### Problem fix/Workaround

None.

#### 26. Maximum operating frequency below 1.76V is 8 MHz

To ensure correct operation, the maximum operating frequency below 1.76V VCC is 8 MHz.

#### Problem fix/Workaround

None, avoid running the device outside this frequency and voltage limitation.



# 37. Datasheet Revision History

Please note that the referring page numbers in this section are referred to this document. The referring revision in this section are referring to the document revision.

## 37.1 8116J - 06/13

Not recommended for new designs - Use ATxmega256A3BU

#### 37.2 8116I - 09/10

1. Updated "Errata" on page 95.

#### 37.3 8116H - 08/10

- 1. Updated Footnote 2 of Figure 2-1 on page 3.
- 2. Updated "Features" on page 28. Event Channel 0 output on port pin 7.
- 3. Updated "Timer/Counter and AWEX functions" on page 50.
- 4. Updated "Alternate Pin Functions" on page 52.
- 5. Updated Table 30-3 on page 52. Pin 15 is VCC.
- 6. Updated "DC Characteristics" on page 64 by adding Icc for Flash/EEPROM Programming.
- 7. Added AVCC in "ADC Characteristics" on page 68.
- 8. Updated Start up time in "ADC Characteristics" on page 68.
- 9. Updated "DAC Characteristics" on page 69. Removed DC output impedence.
- 10 Updated "VBAT and Battery Backup Characteristics" on page 73.
- 11. Updated Figure 35-6 on page 76. Replaced the figure by a correct one.
- 12. Fixed typo in "Errata" section.
- 13. Editorial updates.

## 37.4 8116G - 05/10

- 1. Updated the device pin-out Figure 2-1 on page 3. PDI\_CLK and PDI\_DATA renamed only PDI.
- 2. Deleted page with duplicated information on Production Signature Row in "Production Signature Row" on page 12.
- 3. Changed value for Crystal Oscillator from 32 kHz to 32.768 kHz in "Clock Options" on page 18.
- 4. Updated "DAC 12-bit Digital to Analog Converter" on page 44. DAC uses internal 1.0 voltage.
- 5. Updated "Timer/Counter and AWEX functions" on page 50.



- 6. Updated "Alternate Pin Functions" on page 52.
- 7. Updated "Operating voltage and frequency" on page 66 by replacing SYS to CPU.
- 8. Replaced Table 34-3 on page 67.
- 9. Updated Table 34-3 on page 67, Endurance and Data Retention.
- 11. Updated "PAD Characteristics" on page 70. Input hysteresis is in V and not in mV.
- 12. Added new table "Maximum load capacitance (CL) and ESR recommendation for 32.768 kHz Crystal" on page 72.
- 13. Added new table "Device wake-up time from sleep" on page 72.
- 14. Updated Table 34-20 on page 73.
- 15. Changed Internal Oscillator Speed to "Oscillators and Wake-up Time" on page 90.
- 16. Added characterization for PDI speed in Figure 35-42 on page 94.
- 17. Updated "Errata" on page 95.

## 37.5 8116F - 09/09

- 1. Updated "DC Characteristics" on page 64.
- 2. Added "Flash and EEPROM Memory Characteristics" on page 67.
- 3. Added "" on page 72.
- 4. Upddated "Errata" on page 95.

## 37.6 8116E - 06/09

- 1. Updated "Electrical Characteristics" on page 64.
- 2. Added "Typical Characteristics" on page 74.
- 3. Updated "Errata" on page 95.

#### 37.7 8116D - 04/09

- 1. Updated "Ordering Information" on page 2.
- 2. Editorial updates.

# 37.8 8116C - 02/09

1. Added "Errata" on page 95 for ATxmega256A3B rev B.



# 37.9 8116B - 12/08

1. Added "Errata" on page 95 for ATxmega256A3B rev A.

# 37.10 8116A - 11/08

1. Initial version.



# **Table of Contents**

	Features	1
	Typical Applications	1
1	Ordering Information	2
2	Pinout/Block Diagram	3
3	Overview	4
	3.1Block Diagram	5
4	Resources	<del>6</del>
	4.1Recommended reading	6
5	Disclaimer	<del>6</del>
6	AVR CPU	7
	6.1Features	7
	6.2Overview	7
	6.3Register File	8
	6.4ALU - Arithmetic Logic Unit	8
	6.5Program Flow	8
7	Memories	9
	7.1Features	9
	7.20verview	9
	7.3In-System Programmable Flash Program Memory	10
	7.4Data Memory	10
	7.5Production Signature Row	12
	7.6User Signature Row	12
	7.7Flash and EEPROM Page Size	13
8	DMAC - Direct Memory Access Controller	. 14
	8.1Features	14
	8.2Overview	14
9	Event System	. 15
	9.1Features	15
	9.2Overview	15
10	System Clock and Clock options	. 17
	10.1Features	17



	10.20verview	17
	10.3Clock Options	18
11	Power Management and Sleep Modes	20
	11.1Features	20
	11.2Overview	20
	11.3Sleep Modes	20
12	System Control and Reset	22
	12.1Features	22
	12.2Resetting the AVR	22
	12.3Reset Sources	22
	12.4WDT - Watchdog Timer	23
13	Battery Backup System	24
	13.1Features	24
	13.2Overview	24
14	PMIC - Programmable Multi-level Interrupt Controller	26
	14.1Features	26
	14.2Overview	26
	14.3Interrupt vectors	26
15	I/O Ports	28
	15.1Features	28
	15.2Overview	28
	15.3I/O configuration	28
	15.4Input sensing	31
	15.5Port Interrupt	31
	15.6Alternate Port Functions	31
16	T/C - 16-bit Timer/Counter with PWM	32
	16.1Features	32
	16.2Overview	32
17	AWEX - Advanced Waveform Extension	34
	17.1Features	34
	17.2Overview	34
18	Hi-Res - High Resolution Extension	35
	18 1Features	35



	18.20verview	35
19	RTC32 - 32-bit Real-Time Counter	36
	19.1Features	36
20	TWI - Two Wire Interface	37
	20.1Features	37
	20.2Overview	37
21	SPI - Serial Peripheral Interface	38
	21.1Features	38
	21.20verview	38
22	USART	39
	22.1Features	39
	22.20verview	39
23	IRCOM - IR Communication Module	40
	23.1Features	40
	23.2Overview	40
24	Crypto Engine	41
	24.1Features	41
	24.20verview	41
25	ADC - 12-bit Analog to Digital Converter	42
	25.1Features	
	25.20verview	42
26	DAC - 12-bit Digital to Analog Converter	44
	26.1Features	44
	26.20verview	44
27	AC - Analog Comparator	45
	27.1Features	
	27.20verview	
	27.3Input Selection	47
	27.4Window Function	47
28	OCD - On-chip Debug	48
	28.1Features	48
	28 2Overview	48



29	Program and Debug Interfaces	49
	29.1Features	49
	29.2Overview	49
	29.3JTAG interface	49
	29.4PDI - Program and Debug Interface	49
30	Pinout and Pin Functions	50
	30.1Alternate Pin Function Description	50
	30.2Alternate Pin Functions	52
31	Peripheral Module Address Map	57
32	Instruction Set Summary	58
33	Packaging information	62
	33.164A	62
	33.264M2	63
34	Electrical Characteristics	64
	34.1Absolute Maximum Ratings*	64
	34.2DC Characteristics	64
	34.3Operating Voltage and Frequency	66
	34.4Flash and EEPROM Memory Characteristics	67
	34.5ADC Characteristics	68
	34.6DAC Characteristics	69
	34.7Analog Comparator Characteristics	69
	34.8Bandgap Characteristics	69
	34.9Brownout Detection Characteristics	
	34.10PAD Characteristics	
	34.11POR Characteristics	
	34.12Reset Characteristics	
	34.13Oscillator Characteristics	
	34.14VBAT and Battery Backup Characteristics	73
35	Typical Characteristics	74
	35.1Active Supply Current	
	35.2Idle Supply Current	
	35.3Power-down Supply Current	
	35.4Power-save Supply Current	82
	35.5Pin Pull-up	82



	35.6Pin Output Voltage vs. Sink/Source Current	84
	35.7Pin Thresholds and Hysteresis	87
	35.8Bod Thresholds	89
	35.9Oscillators and Wake-up Time	90
	35.10Module current consumption	93
	35.11Reset Pulsewidth	94
	35.12PDI Speed	94
36	Errata	95
	36.1ATxmega256A3B	95
37	Datasheet Revision History	101
	37.18116J - 06/13	101
	37.28116I - 09/10	101
	37.38116H - 08/10	101
	37.48116G - 05/10	101
	37.58116F - 09/09	102
	37.68116E - 06/09	102
	37.78116D - 04/09	102
	37.88116C - 02/09	102
	37.98116B - 12/08	103
	37.108116A - 11/08	103
	Table of Contents	i



## Headquarters

Atmel Corporation

2325 Orchard Parkway San Jose, CA 95131 USA

Tel: 1(408) 441-0311 Fax: 1(408) 487-2600

#### International

Atmel Asia

Unit 1-5 & 16, 19/F BEA Tower, Millennium City 5 418 Kwun Tong Road Kwun Tong, Kowloon Hong Kong

Tel: (852) 2245-6100 Fax: (852) 2722-1369 Atmel Europe

France

Le Krebs 8, Rue Jean-Pierre Timbaud BP 309 78054 Saint-Quentin-en-Yvelines Cedex

Tel: (33) 1-30-60-70-00 Fax: (33) 1-30-60-71-11

Atmel Japan

9F, Tonetsu Shinkawa Bldg. 1-24-8 Shinkawa Chuo-ku, Tokyo 104-0033 Japan

Tel: (81) 3-3523-3551 Fax: (81) 3-3523-7581

#### **Product Contact**

Web Site

www.atmel.com

Technical Support

avr@atmel.com

Sales Contact

www.atmel.com/contacts

Literature Requests

www.atmel.com/literature

Disclaimer: The information in this document is provided in connection with Atmel products. No license, express or implied, by estoppel or otherwise, to any intellectual property right is granted by this document or in connection with the sale of Atmel products. EXCEPT AS SET FORTH IN ATMEL'S TERMS AND CONDITIONS OF SALE LOCATED ON ATMEL'S WEB SITE, ATMEL ASSUMES NO LIABILITY WHATSOEVER AND DISCLAIMS ANY EXPRESS, IMPLIED OR STATUTORY WARRANTY RELATING TO ITS PRODUCTS INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTY OF MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE, OR NON-INFRINGEMENT. IN NO EVENT SHALL ATMEL BE LIABLE FOR ANY DIRECT, INDIRECT, CONSEQUENTIAL, PUNITIVE, SPECIAL OR INCIDENTAL DAMAGES (INCLUDING, WITHOUT LIMITATION, DAMAGES FOR LOSS OF PROFITS, BUSINESS INTERRUPTION, OR LOSS OF INFORMATION) ARISING OUT OF THE USE OR INABILITY TO USE THIS DOCUMENT, EVEN IF ATMEL HAS BEEN ADVISED OF THE POSSIBILITY OF SUCH DAMAGES. Atmel makes no representations or warranties with respect to the accuracy or completeness of the contents of this document and reserves the right to make changes to specifications and product descriptions at any time without notice. Atmel does not make any commitment to update the information contained herein. Unless specifically provided otherwise, Atmel products are not suitable for, and shall not be used in, automotive applications. Atmel's products are not intended, authorized, or warranted for use as components in applications intended to support or sustain life.

© 2009 Atmel Corporation. All rights reserved. Atmel<sup>®</sup>, logo and combinations thereof, AVR<sup>®</sup> and others are registered trademarks, XMEGA<sup>TM</sup> and others are trademarks of Atmel Corporation or its subsidiaries. Other terms and product names may be trademarks of others.